

To: 1 010125
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,375-00-00 ^{208R}
NW SW, SEC. 35, T 29 S, R 11 ^(W)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corp.
Name & Address 155 N. Market, Suite 1000
Wichita, KS 67202

1980 feet from S section line
4620 feet from E section line
Lease Name Inslee Well # 1
County Pratt 95.88
Well Total Depth 2950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well _____ Gas Well x Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor TXO Production Corp. License Number 5171

Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 9:40 am Day: 18 Month: April Year: 19 86

Plugging proposal received from Jerry Collins

(company name) TXO (phone) 316-886-5606

were: 4 1/2" at 2840' PBT 2807' Perfs at 2704-14'

Pump 1 sack hulls, 25 sx cement, release 8 5/8" rubber plug and pump 9 sx gel and 100 sx cement. Pump 100 sx cement down annulus

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 18 Month: April Year: 19 86

ACTUAL PLUGGING REPORT Pumped 1 sack hulls, 25 sx cement, 4 sx gel and 60 sx cement.

Pumped 140 sx cement down backside - Maximum pressure 750 psi and shut in 350 psi

Maximum pressure 1800 psi and shut in 1300 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel 2% cc by BJ-Titan.
(If additional description is necessary, use BACK of this form.)

(If desired, you should observe this plugging.)

INVOICED

DATE APR 29 1986

INV. NO. 13607

4-18 MAY 28 1986

Signed Jack P. [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1986 4-28-86
CONSERVATION DIVISION
Wichita, Kansas