

1 060057

2-3

42

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-22,033-00-00
SW NW NE, SEC. 19, T 29 S, R 11 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License / 8458

4290 feet from S section line

2310 feet from E section line

Operator: Trans-Western Petroleum, Inc.
Name & Address P.O. Box 276

Lease Name Blackwelder Well / 1

County Pratt 153.23

Golden, CO 80402-0276

Well Total Depth 4715 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company, Inc. License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 10:10 p.m. Day: 3 Month: 2 Year: 19 91

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331
Elevation 1858'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 700'

1st plug at 720' with 50 sx cement, 2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 p.m. Day: 3 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1991 02-06-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 3-5-91

INV. NO. 31007

Signed [Signature] (TECHNICIAN)

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date January 26, 1991
 month day year

SW NW NE Sec 19 Twp 29 S, Rg 11 East West
4290 feet from South line of Section
2310 feet from East line of Section
 (Note: Locate well on Section Plat on Reverse Side)

OPERATOR: License # 8458
 Name: TRANS-WESTERN PETROLEUM, INC.
 Address: P. O. Box 276
 City/State/Zip: Golden, Colorado 80402-0276
 Contact Person: Doug Isern
 Phone: 303/279-2995

County: Pratt
 Lease Name: Blackwelder Well #: 1
 Field Name: Wildcat
 Is this a Prorated Field? yes no
 Target Formation(s): Viola, Arbuckle
 Nearest lease or unit boundary: 990'
 Ground Surface Elevation: 1858 feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Depth to bottom of fresh water: 170'
 Depth to bottom of usable water: 220'
 Surface Pipe by Alternate: X 1 2
 Length of Surface Pipe Planned to be set: 250'
 Length of Conductor pipe required: N/A
 Projected Total Depth: 4700'
 Formation at Total Depth: Arbuckle
 Water Source for Drilling Operations:
 well farm pond other

CONTRACTOR: License #: 5929
 Name: DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OHWO ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes

If OHWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no
 If yes, total depth location: _____

John Armbuster Spud 1-26-91
8 5/8" - 250' DG

AFFIDAVIT

RECEIVED
 STATE COMMISSION

I, John Armbuster hereby affirms that the drilling, completion and eventual plugging of this well 15-15-1-22, 033-00-00 K.S.A. 55-101,

Pusher John Armbuster
 SPUD DATE 1-26-91 INIT. AD
 LENGTH SURFACE PLANNED 250' - 8 5/8" =
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 1 1/2" @ 272' CONDUCTOR
 ANHYDRITE T- B-700 ELEVATION 1858'
 TD 4705' FORMATION _____
 RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ 7 Ft. W/ 49 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 720 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 300 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
 CONSERVATION DIVISION
 Wichita, Kansas
 WATER WELL SX (Irr. Well) Pond _____
 Hauling _____
 TECHNICIAN CM DATE 1-29-91
 TYPE OF CEMENT 60/40 Poz 670
 STARTING TIME 10:10 (AM/PM) DATE 2-3-91
 COMPLETION TIME 11:30 (AM/PM) DATE 2-3-91
 CEMENT COMPANY Allied