

STATE OF KANSAS
 CORPORATION COMMISSION
 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-20,984-6D-00
 LEASE NAME Riffey #2
 WELL NUMBER #2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Hummon Oil Corporation

ADDRESS 400 ONE MAIN PLACE WICHITA, KS. 67202

PHONE#(316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-22-89 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4545

Perfs: 4448-50'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	set at 231'	conductor pipe.
				8 5/8	set at 800'	cemented with 300 sx.
				4 1/2	set at 4541'	cemented with 125 sx. 3268'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
5-25-89: top of sand at 4333'. Cut and pulled 3268' of 4 1/2 inch pipe.
8-24-89: Top hole plugged with 400# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, 1 plug, 100 sx. cement. 60 40 poz. mix., 6% gel. Mx. pressure 250#. 130# shut in pressure.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corp. SEP - 8 1989 09-08-89


STATE OF Kansas COUNTY OF Pratt

CONSERVATION DIVISION
 Wichita, Kansas

Judy Berry (Employee of Pratt Well Service, Inc.)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 7th day of Sept., 19 89

Dorothy M. Ferguson
 Notary Public

My Commission Expires: Feb. 6, 1993

DRILLERS LOG

#2 Riffey

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
10 3/4" cond. pipe @ 231' w/ 275 sx cement	CONTRACTOR:	Big-H Drilling, Inc.	C W/2 E/2 SE/4 Sec. 6-29S-12W Pratt County, KS
8 5/8" @ 800' w/ 300 sx cement	COMMENCED:	September 10, 1981	TOTAL DEPTH: 4545'
4 1/2" @ 4541' w/ 125 sx. cement	COMPLETED:	September 25, 1981	ELEVATION: 1900 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	261	
Shale & Red Bed	261	888	
Shale	888	1275	
Shale & Anhydrite	1275	1710	
Shale	1710	1967	
Shale & Lime	1967	2791	
Lime & Shale	2791	3610	
Shale & Lime	3610	3773	
Lime & Shale	3773	4410	
Lime	4410	4441	
Lime & Sand	4441	4545	
RTD		4545	

STATE RECEIVED
MAY 9 1989
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.

Karen R. Tennis

Karen R. Tennis

Subscribed and sworn to before me this 29th day of September, 1981.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 2/13/82

Sandra L. Mendoza

Notary Public