

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,096-00-00

LEASE NAME Kessler

WELL NUMBER #1

330 Ft. from S Section Line

330 Ft. from W Section Line

SEC. 5 TWP. 29 RGE. 12W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 2-15-00

Plugging Completed 2-22-00

RECEIVED
KANSAS CORP COM
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2000 MAR 13 2:10

3-13-00

LEASE OPERATOR Hummon Corporation

ADDRESS 950 N. Tyler, Wichita, Kansas 67212

PHONE# (316) 773-2300 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SHD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Richard Lacey

(KCC District Agent's Name).

Is ACO-1 filed? _____ if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4685'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	938'	None
				4-1/2"	4544'	2215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 4230' and 4 sks. cement. Shot pipe @2400' and 2215'

ran 1" tubing on the backside of the 8-5/8" and circulated 80 sks. 60/40 pos. 6% gel to the top. Pulled 4-1/2" casing to 960', pumped 15 sks. gel and 50 sks. cement, pulled up to 450', pumped 40 sks. cement, pulled to 250' and circulated 40 sks. cement. 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

I, above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 10th day of March, 2000

Irene Herzberg
Notary Public

My Commission Expires: _____

