

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,304-00-00  
LEASE NAME Neel  
WELL NUMBER 3  
660 ft. from S Section Line  
1980 ~~1680~~ ft. from E Section Line  
SEC. 4 TWP. 29 RGE. 12 (E or W)  
COUNTY Pratt

RECEIVED  
JUN 05 2002  
06-05-02  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

LEASE OPERATOR Younger Energy Company  
ADDRESS 453 S. Webb, Suite 100, Wichita, KS 67207  
PHONE # (316 ) 681-2542 OPERATORS LICENSE NO. 30705  
Character of well oil

Date Well Completed \_\_\_\_\_  
Plugging Commenced 5/23/02  
Plugging Completed 5/29/02

(Oil, Gas, D&A, SWD, input, Water Supply Well)  
The plugging proposal was approved on 5/23/02 (date)  
by Steve Durant (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4334

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS							CASING RECORD						
Formation	Content	From	To	Size	Put in	Pulled out							
				8 5/8	387	none							
				5 1/2	4325	2830							

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

Sand at 4170, bailed 5 sacks cement. Shot pipe at 3010, 2830, worked pipe free. Pulled 50 joints, pumped 50 sacks cement with 10 sacks gel. Pulled to 410, pumped 50 sacks cement. Pulled to 40', pumped 10 sacks cement. Laid joint down.


Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES : Younger Energy Company  
STATE OF KANSAS COUNTY OF SEDGWICK, ss.

DIANE REBSTOCK (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says : That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Diane Rebstock  
(Address) 453 S. Webb #100, Wichita, KS 67207

SUBSCRIBED AND SWORN TO before me 4th day of June, 2002



Stacey L. Williamson  
Notary Public

My commission Expires :

OR