

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Pratt

County. Sec. 3 Twp. 29 Rge. 12 ~~EX~~ (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE

Lease Owner Herndon Drilling Company

Lease Name B. E. Blair #1 Well No.

Office Address 423 Mayo Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 11-3 1953

Application for plugging filed 11-3 1953

Application for plugging approved 11-3 1953

Plugging commenced 11-3 1953

Plugging completed 11-3 1953

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4563 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	762	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud to 300 ft. Set plug @ 300 ft. Pumped 20 sacks cement then drilled pipe by Halliburton on plug. Filled with mud to 30 ft. below surface. Set plug @ 30 ft Filled with cement to surface

11-14-53
NOV 14 1953
CONSERVATION
WELL

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Herndon Drilling Company
Address Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.
W. G. Prather (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. G. Prather*

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1953

My commission expires Sept. 19, 1956
Notary Public. *[Signature]*

24-7366-5 3-53-20M
PLUGGING
FILE SEC 3 T 29 R 12A
BOOK PAGE 141 LINE 6

WELL LOG ON BLAIR #1

Spudding date: 10/19/53
 Date casing set: 10/19/53
 Date rotary completed: 11/3/53
 Date cable completed:

Location:
 Sec. 3-29S-12W - Pratt County, Kansas

FROM	TO	FORMATION	REMARKS
0	120	Surface Hole	
120	747	Shale & Shells	
747	762	Anhydrite	Ran 24 Jts. 8-5/8" 24# Casing @ 762'
762	1685	Shale & Shells	Cemented w/ 450 Sx. Pozmix
1685	1776	Sandy Shale	and 500# CC
1776	1872	Shale & Shells	
1872	2170	Lime & Shale	
2170	2320	Sandy Lime	
2320	2450	Sandy Lime & Shale	
2450	3300	Lime & Shale	
3300	3690	Lime	
3690	3827	Lime & Shale	
3827	4308	Lime	
4308	4370	Lime & Chert	
4370	4573	Lime	
4573		Total Depth	

Plugging Hole

RECEIVED
 STATE COMMISSION
 NOV 14 1953
 CONSERVATION

Subscribed and sworn to, before me this 10th
 day of November, 19 53

I certify the above and foregoing to be a true and exact
 copy of the original driller's log on the BLAIR #1

Patsy M. Mearns
 Notary Public
 My commission expires: 4-22-57

HERNDON DRILLING COMPANY
O. J. Moore
 By: _____
 Title: Assistant Secretary

PLUGGING
 FILE SEC 3 T 29 R 12W
 BOOK PAGE 141 LINE 6