


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pratt County. Sec. 35 Twp. 29S Rge. 11W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NE NW  
Lease Owner Phillips Petroleum Company  
Lease Name Thompson Well No. J#1  
Office Address Box 287, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-24-64 19  
Application for plugging filed 8-24-64 19  
Application for plugging approved 8-24-64 19  
Plugging commenced 8-24-64 19  
Plugging completed 8-24-64 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4804 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357.92'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300' Plug 1/2 sk. hulls 20 sks. cement  
Mud to 40' Plug 1/2 sk. hulls 10 sks. cement  
2 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

08-31-64 AUG 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie Kite

P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1964

Ulonda Nichols

My commission expires

April 1, 1967

Ulonda Nichols

Notary Public.

DRILLER'S LOG

COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 31 1964

COMMENCED:  
COMPLETED:

CONSERVATION DIVISION  
Wichita, Kansas

Phillips Petroleum Company  
LEBEN DRILLING, INC.  
THOMPSON J-#1  
C NE NW Sec. 35-29S-11W  
PRATT COUNTY, KANSAS  
8-10-64  
8-24-64

0	170	Sand
170	230	Redbed
230	365	Shale with Lime Streaks
365	520	Redbed & Sand
520	1620	Shale & Shells
1620	1655	Anhydrite
1655	3755	Shale & Lime
3755	3870	Lime
3870	3930	Lime with Shale Streaks
3930	4237	Lime
4237	4335	Lime & Shale
4335	4404	Lime
4404	4425	Lime & Shale
4425	4525	Lime & Chert
4525	4670	Lime & Shale
4670	4688	Lime (Simpson top 4688)
4688	4722	Sand & Shale, Lime
4722	4775	Sandy Lime & Shale
4775	4798	Simpson Arbuckle
4798	4804	Arbuckle
	<u>4804</u>	<u>Rotary Total Depth - D. &amp; A.</u>

Set 8 5/8" new surface casing @ 357.92' with landing joint cemented with 110 sacks Common 20% Diacel added with 200# c.c. 50 sacks Common 100# c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Thompson J-#1 well, located C NE NW of Section 35, Township 29 South, Range 11 West, Pratt County, Kansas, as reflected by the files of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 26th day of August, 1964.

*Ulanda Nichols*

Ulanda Nichols

My Commission Expires  
April 1, 1967