

API NUMBER 15-151-20,375-00-00

LEASE NAME Inslee

WELL NUMBER #1

1980' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 35 TWP. 29S RGE. 11 (W)

COUNTY Pratt

Date Well Completed 4-29-77

Plugging Commenced 4-18-86

Plugging Completed 4-18-86

LEASE OPERATOR TXO Production Corp.

ADDRESS 155 N. Market, Suite 1000, Wichita, KS 67202

PHONE# (316) 269-7600 OPERATORS' LICENSE NO. 5171

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Unknown

Is ACO-1 filed? YES if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 2950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8-5/8"	294'	
	Production			4-1/2"	94 jts	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well w/ 1 sx hulls & 25 sxs 60/40 poz, 6% gel & 2% CaCl, 4 sxs gel, 60 sxs 60/40 poz w/ 6% gel & 2% CaCl, 140 sxs down annulus. Plugging complete @ 10:30 a.m. on 4-18-86.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Well Services License No. 5105

Address 107 W. Fowler, Medicine Lodge, KS. 67104

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles A. Paulson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles A. Paulson

(Address) 155 N. Mkt. #1000, Wichita, KS. 67202

SUBSCRIBED AND SWORN TO before me this 29th day of May, 1986

Connie F. Koehler
 Notary Public

My Commission Expires: July 10, 1988

Connie F. Koehler
 NOTARY PUBLIC
 State of Kansas
 MY APPT. EXPIRES 7/10/88

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 30 1986
 CONSERVATION DIVISION
 Wichita, Kansas

KANSAS DRILLERS LOG

S. 35 T. 29S R. 11 E
 Loc. 1980' FSL & 660' FWL
 County Pratt

API No. 15 — 151 — 20,375
 County Number

Operator
 Texas Oil & Gas Corp.

Address
 200 West Douglas, Suite 300, Wichita, Kansas 67202


Well No. 1 Lease Name Inslee

Footage Location
1980 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor Xplor Drilling Company Geologist High Plains Consulting Ltd.

Spud Date 3-18-77 Total Depth 2950' P.B.T.D. 2807'

Date Completed 4-29-77 Oil Purchaser N/A



Elev.: Gr. 1807'
 DF 1812' KB 1815'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	294'	Common	250	2% Gel, 3% CaCl
Production	7 7/8"	4 1/2"	10.5#	2840'	50/50 Pozmix	150	18% NaCl, 1.25% CFR-2, 5# Gilsoni

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD			2 JSPF	Deep Penet.	2704-14'
Size	Setting depth	Packer set at			
2 3/8"	2607'	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION Wichita, Kansas
Acidized w/1750 gallons acid & frac w/20,000 gallons & 13,000# sand.	MAR-24 1986

INITIAL PRODUCTION

Date of first production Shut-in		Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	N/A	380	24	N/A	
Disposition of gas (vented, used on lease or sold) Shut-in			Producing interval(s) 2704-14'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.