

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-15-21,959-00-00  
Neumann-Wheatley Farms,  
LEASE NAME Inc. 1-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-1  
660' Ft. from S Section Line  
3300' Ft. from E Section Line

LEASE OPERATOR Thomas E. Black, d/b/a Black Petroleum Company SEC. 1 TWP. 29 SRGE. 12 W. (E or W)

ADDRESS P. O. Box 12922  
Wichita, Kansas 67277

COUNTY Pratt

PHONE# (316) 942-2741 OPERATORS LICENSE NO. 5068

Date Well Completed 12-5-89  
3:15 AM

Character of Well D & A

Plugging Commenced 12-5-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

4:30 AM  
Plugging Completed 12-5-89

The plugging proposal was approved on December 4, 1989 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing Formation                      Depth to Top                      Bottom                      T.D. 4690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.  
Filled hole with heavy mud. Heavy mud to 700' with 50 sacks through open ended drill pipe at 700'; with 40 sacks at 290' through open ended drill pipe; with 10 sacks 40' to surface. with 15 sacks in rathole. Used 50/50 Pozmix wutg 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P. O. Box 129  
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner

(Address) STERLING DRILLING COMPANY  
P. O. Box 129, Sterling, Kansas

SUBSCRIBED AND SWORN to before me this 6th day of December, 19 89



Agnes D. Wurst  
Notary Public

My Commission Expires: 4-26-93

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - NEUMANN-WHEATLEY FARMS, Inc. 1-1'

Located: C SE SW, Section 1-29S-12W, Pratt County, Kansas

OWNER: Thomas E. Black, d/b/a Black Petroleum Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 29, 1989

COMPLETED: December 5, 1989

TOTAL DEPTH: 4690'

## LOG

0 - 210 Sand and Clay

210 - 515 Red Bed

515 - 4690 Lime and Shale

## CASING RECORD

Ran 6 joints 8 5/8" casing. 245.86'  
pipe set at 259' K.B. Cemented with  
200 sacks 60/40 Pozmix, 2% gel and  
3% cc. Plug down at 11:45 AM, 11-25-89,  
by Howco.

Plugged.

Deviation Surveys: 1° at 2725'  
3/4° at 3854'

RECEIVED  
STATE CONSERVATION COMMISSION

DEC 12 1989

CONSERVATION DIVISION  
Wichita, Kansas