

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 21 Twp. 29S Rge. 11W E4W
Location as "NE/CNW1/4SW1/4" or footage from lines
660' FSL; 440' FWL, NW/4

Lease Owner F. G. Holl
Lease Name Hageman #1-21 Well No. 1-21

Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed October 20, 1978 19'
Application for plugging filed October 19, 1978 19'
Application for plugging approved October 19, 1978 19'
Plugging commenced 12:30 AM, October 20, 1978 19'
Plugging completed 1:45 AM, October 20, 1978 19'
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Depth to top Bottom Total Depth of Well 2850'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 480' with 30 sacks through
drill pipe; heavy mud to 240' with 25 sacks
through drill pipe; heavy mud to 40' with
Howco plug and 1/4 sack hulls with solid bridge.
10 sacks to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.


F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579

Subscribed and sworn to before me this 21st day of

October 1978 STATE CORPORATION COMMISSION

My commission expires



Charles M. Hall, Notary Public

CONSERVATION DIVISION
Wichita, Kansas
11-06-78

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- HAGEMAN #1-21
Located: 660' FSL; 140' FSL, NW/4, Section 21-298-11W,
Pratt County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 11, 1978
COMPLETED: October 20, 1978

TOTAL DEPTH: 2850'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 29	Clay	Run 6 joints used 23#, 7" casing, 259.70' set at 261' G.L. with 150 sacks 60/LB Pomix with 3% cc. Plug down at 9:00 PM, 10-11-78, by Howco.
29 - 1736	Shale	
1736 - 2529	Lime and Shale	
2529 - 2730	Shale	
2730 - 2800	Shale and Lime	
2800 - 2850	Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 6 1978

CONSERVATION DIVISION
Wichita, Kansas