


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Pratt County. Sec. 20 Twp. 29S Rge. 11W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
660' ESL; 330' FWL, SE/4  
Lease Owner F. G. Holl  
Lease Name Miller #1-20 Well No. 1  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole)

Lost Hole  
Date Well completed September 18, 1978 19  
Application for plugging filed September 17, 1978 19  
Application for plugging approved September 17, 1978 19  
Plugging commenced 1:00 AM-September 18, 1978 19  
Plugging completed 2:30 AM-September 18, 1978 19  
Reason for abandonment of well or producing formation

Lost Hole  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation Depth to top Bottom Total Depth of Well 2408'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS						CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT	
				7"	261'	None	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.  
Heavy mud to 480' with 30 sacks through open end drill pipe. Heavy mud to 240' with 25 sacks through open end drill pipe. Heavy mud to 40' with Howco plug and 1/4 sack hulls and solid bridge with 10 sacks to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.  
Bernard Laudermilk (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk  
Bernard Laudermilk, President  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September 1978

My commission expires  
CHARLES M. HALL  
Rice County, Ks.  
My Appt. Exp. Jan. 31, 1982

Charles M. Hall, Notary Public.

CHARLES M. HALL  
Rice County, Ks.  
My Appt. Exp. Jan. 31, 1982

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1978  
9-21-78  
CONSERVATION DIVISION  
Wichita, Kansas

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- MILLER #1-20

Located: 660' ESL; 330' FWL, SE/4, Section 20-29S-11W,  
Pratt County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 12, 1978  
COMPLETED: September 18, 1978

TOTAL DEPTH: 2408'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 265 Sand and Shale	Ran 6 joints of 7" O.D. used casing.
265 - 1285 Shale	259.74' pipe set at 261' G.L. Cemented
1285 - 1293 Anhydrite	with 175 sacks of 60/40 Pozmix with 3%
1293 - 1860 Shale	cc. Plug down at 11:45 PM, 9-12-78.
1860 - 2395 Lime and Shale	
2395 - 2408 Lime	Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 21 1978

CONSERVATION DIVISION  
Wichita, Kansas