


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pratt County, Sec. 20 Twp. 29S Rge. 11W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE NW

Lease Owner F. G. Holl  
Lease Name Tipton #1-20 Well No. 1-20  
Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed November 6, 19 81  
Application for plugging filed November 6, 19 81  
Application for plugging approved November 6, 19 81  
Plugging commenced 11:30 AM November 6, 19 81  
Plugging completed 1:15 PM November 6, 19 81  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie  
Producing formation Depth to top Bottom Total Depth of Well 4460'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it/into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.

Heavy mud to 600' with 50 sacks 50/50 Pozmix with 4% gel  
and 3% cc through open ended drill pipe at 600'; heavy  
mud to 280' with 40 sacks through open ended drill pipe;  
heavy mud to 40' with solid bridge at 40'; Howco plug  
and 1/2 sack hulls' 10 sacks to surface and 10 sacks in  
rathole. Left water well for Farmer: Darell Brant,

Rural Route  
Isabel, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-81  
NOV 16 1981  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF X RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
STERLING DRILLING COMPANY  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 81.



Agnes D. Wurst  
Agnes D. Wurst, Notary Public.

My commission expires \_\_\_\_\_

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG - - - - - TIPTON #1-20

Located: C SE NW, Section 20-29S-11W, Pratt County,  
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 27, 1981

COMPLETED: November 6, 1981

TOTAL DEPTH: 4460'

LOG

CASING RECORD

0 - 309 Sand and Clay  
309 - 320 Shale, Shells  
320 - 1030 Shale  
1030 - 2765 Lime and Shale  
2765 - 2805 Lime  
2805 - 3760 Lime and Shale  
3760 - 3865 Lime  
3865 - 4045 Lime and Shale  
4045 - 4225 Lime  
4225 - 4385 Lime and Shale  
4385 - 4460 Lime

Ran 7 joints 8 5/8", 23# new OD casing.  
294.47' pipe set at 305' K.B. Cemented  
with 250 sacks 60/40 Pozmix with 3% cc.  
Plug down at 10:00 PM, 10-27-81, by Howco.

Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1981

CONSERVATION DIVISION  
Wichita, Kansas

Deviation Surveys: 2 1/2° at 1770'  
2° at 3176'  
2 1/2° at 4460'