


# WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Pratt County. Sec. 18 Twp. 29 Rge. (E) 11 (W)  
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  NE $\frac{1}{4}$  SE $\frac{1}{4}$   
 Lease Owner **Cities Service Oil Company**  
 Lease Name **Blackwelder** Well No. **1**  
 Office Address **Bartlesville, Oklahoma**  
 Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**  
 Date well completed **November 25, 1950**  
 Application for plugging filed **November 25, 1950**  
 Application for plugging approved **November 25, 1950**  
 Plugging commenced **November 26, 1950**  
 Plugging completed **November 26, 1950**  
 Reason for abandonment of well or producing formation **Dry Hole**  
 If a producing well is abandoned, date of last production **-----** 19**-----**  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? **C. D. Stough**



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well **-----**  
 Producing formation **Arbuckle** Depth to top **4655'** Bottom **4700'** Total Depth of Well **4700'** Feet  
 Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	348'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from **-----** feet to **-----** feet for each plug set.

**4700' to 300' heavy mud.**  
**300' to 240' wood plug and 20 sacks cement.**  
**240' to 35' heavy mud**  
**35' to base of cellar, 10 sacks cement.**

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 7 - 1950  
 CONSERVATION DIVISION  
 WICHITA, KANSAS  
 12-07-50

(If additional description is necessary, use BACK of this sheet)  
 Correspondence regarding this well should be addressed to **R. C. Cooper**  
 Address **Box 751**  
**Great Bend, Kansas**

STATE OF **Kansas**, COUNTY OF **Barton**, ss.  
**V. M. Conover** (employee of owner) on ~~oath~~ of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. M. Conover*  
**Box 751, - Great Bend, Kansas**  
 (Address)

SUBSCRIBED AND SWORN TO before me this **4th** day of **December**, 19 **50**  
*W. G. Smith* Notary Public.  
 My commission expires **March 12, 1951.**

**PLUGGING**  
 FILE SEC. 18 T. 29 R. 11 W.  
 BOOK PAGE 45 LINE 5

# WELL RECORD

Company Cities Service Oil Company Well No. 1 Farm Blackweider  
 Location 990' South & 330' West of S/L Corner Sec. 18 T. 29 R. 11W  
 Elevation 1842 (1899 Gr.) County Pratt State Kansas  
 Initial Prod. None - Dry Hole; P. & A. 11-25-50 Contractor Holm Drilling Company  
 Acid None Drig. Comm. November 3, 1950  
 T. D. 4700' Drig. Comp. November 25, 1950

**CASING RECORD:**

2-5/8" @ 348' con. 250 wacks cement

**FORMATION RECORD:**

surface soil	0-10
sand	60
sand & shale	150
sandy shale	170
red bed	354
sand & shale	670
anhydrite	690
shale & red bed	1079
shale & shells	1320
salt & shale	1570
shale & shells	1750
lime & shale	2115
lime	2140
lime & shale	2170
shale & shells	2640
lime & shale	2830
shale	2955
shale & lime	3085
lime & shale	3170
shale & lime	3295
lime & shale	3990
lime	3690
lime & shale	3795
sand	3804
lime	3808
lime & shale	3844
lime	4300
lime, shale & chert	4314
lime & shale	4346
shale, lime & chert	4369
conglomerate	4396
lime & shale	4450
shale & lime	4460
lime	4505
lime & chert	4560
sand & lime	4567
shale	4569(1)
shale, lime &	4583

**PLUGGING**  
 FILE SEC. 18 T. 29 R. 11W  
 PAGE 65 LINE 15023

lime & chert	4557
shale & sand	4609
sand & shale	4642
lime & shale	4690
lime	(T. D.) 4700
Topoka	3281'
Lansing	3840'
Cherty Conglomerate	4295'
Kindershook	4368'
Viola	4458'
Simpson (Sand)	4544'
Arbuckle	4655'
Penetration	45'
Total Depth	4700'

Drill stem test 3976-87 rec. 10' mud in 30 mins.

Drill stem test 4021-37 rec. 1632' salt water in 30 mins., BHP 1675#.

SYNO: 500' 00  
 1000' 00  
 1500' 00  
 2000' 00  
 2500' 00  
 3000' 00  
 3500' 00  
 4000' 00  
 4500' 10

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 DEC 7 - 1950  
 CONSERVATION DIVISION  
 Wichita, Kansas