

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,428 <sup>00-00</sup>

LEASE NAME Blackwelder

WELL NUMBER 1-15

SPOT LOCATION SW SW SE

SEC. 15 TWP. 29S RGE. 15 ~~W~~ (W)

COUNTY Pratt

Date Well Completed 6-17-84

8:00 AM

Plugging Commenced 6-17-84

9:45 AM

Plugging Completed 6-17-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg  
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well \_\_\_\_\_  
(Oil, Gas D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4796'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Filled hole with heavy mud.  
Heavy mud to 1080'; 50 sacks at 1080'. Heavy mud to 300'; 50 sacks at 300'.  
Heavy mud to 40'; bridge, sack of hulls, solid plug and 10 sacks at 40'.  
10 sacks in rathole and 10 sacks in mousehole. Used 60/40 Pozmix, 2% gel and 3% cc.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
STERLING DRILLING COMPANY


(Address) F. A. Wuellner, Secretary  
P. O. Box 129

Sterling, Kansas 67579

SUBSCRIBED AND SWORN TO before me this 18 day of June, 1984.

[Signature]  
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1984  
6-22-84  
CONSERVATION DIVISION  
Wichita, Kansas

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - BLACKWELDER #1-15

Located: SW SW SE, Section 15-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl

ROTAREY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 7, 1984

COMPLETED: June 17, 1984

TOTAL DEPTH: 4796'

## LOG

## CASING RECORD

0 - 165	Sand and Clay	Ran 6 joints new 8 5/8", 23# casing.
165 - 268	Red Bed	253.46' pipe set at 261' K.B. Cemented
268 - 380	Clay, Red Bed, Shale	with 200 sacks Common, with 2% gel and
380 - 1680	Shale	3% cc. Plug down at 9:30 PM, 6-7-84,
1680 - 1960	Shale and Lime Stringers	by Howco.
1960 - 2694	Lime and Shale	
2694 - 2720	Indian Dave	
2720 - 4796	Lime and Shale	Plugged.

Deviation Surveys: 1° at 1993'  
1 3/4° at 2720'  
1° at 4060'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1984

CONSERVATION DIVISION  
Wichita, Kansas