

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-22,065-00-00

LEASE NAME Hirt

WELL NUMBER 1-15

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 15 TWP. 29S RGE. (X) or (W)

COUNTY Pratt

Date Well Completed 11-7-91

Plugging Commenced 4:00 p.m. 11-7-91

Plugging Completed 5:00 p.m. 11-7-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G.Holl Company

ADDRESS P.O. Box 780167
Wichita, Kansas 67278-0167

PHONE#(316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, (D&A), SWD, Input, Water Supply Well)

The plugging proposal was approved on October 28, 1991 (date)

by Richard Lacey; Steve Pfeifer was present when plugged 11-7-91 (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? yes

Producing Formation Depth to Top Bottom T.D. 4784'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	262	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled hole with heavy mud, Plugged with 50 sacks at 700', 40 sacks at 300', 15 sacks at 60' to surface, all plugs through open ended drill pipe, and 15 sacks in the rathole used 60X40 pozmix with 6% gel. by Halliburton

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P.O. Box 129, Sterling, Kansas 67579

STATE OF Kansas COUNTY OF Rice, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements and contents contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOV 12 1991

(Signature) Richard L. Mead
Richard L. Mead, President
(Address) P.O. Box 129, Sterling, Ks. 67579

CONSERVATION DIVISION
WICHITA, KS

AND SWORN TO before me this 8 day of November, 19 91

F.A. Wuellner
F.A. Wuellner Notary Public

My Commission Expires:



STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

November 8, 1991

SAMPLE LOG Located NW-SW-NE Sec. 15, T 29S R 11W, Pratt County, Kansas Hirt Farms 1-15

OWNER: F.G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 28, 1991

COMPLETED: November 7, 1991

TOTAL DEPTH: 4874' R.T.D.
4873' L.T.D

LOG

0' - 175'	Surface Soil & Sand
175' - 265'	Red Bed
265' - 1968	Shale
1968' - 4874'	Lime & Shale

CASING RECORD

Spud at 8:30 a.m. 10-28-91.
Drilled 265' of 12½" hole
Ran 6 joints of 8 5/8", 23#
New Casing, 248.85' pipe, Set
at 262' K.B. cemented with 225
sacks of 60 X 40 Pozmix with
2% Gel. & 3% CC. Plug down at
1:15 p.m., October 28, 1991. By
Howco. Good returns to surface.

Plugged.

RECEIVED

KANSAS CORPORATION COMMISSION

NOV 12 1991

CONSERVATION DIVISION
WICHITA, KS

DEVIATION SURVEYS

1° at 4154'
1½° at 4784'