

TYPE AFFIDAVIT OF COMPLETION FORM ACO-1 WELL HISTORY
SIDE ONE Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238. No Log

LICENSE # 5286 EXPIRATION DATE September 4, 1983

OPERATOR Horizon Petroleum Corporation API NO. 15-097-20,578-A

ADDRESS Riverfront Place, 833 N. Waco COUNTY Kiowa

Wichita, KS 67203 FIELD Pyle NE

** CONTACT PERSON Jerry Hoggatt PROD. FORMATION N/A
PHONE 316 - 267-8416

PURCHASER N/A LEASE Starkey
cc-kcc

ADDRESS WELL NO. 1

DRILLING H-30, Inc. 1650 Ft. from South Line and

CONTRACTOR CONTRACTOR ADDRESS 251 N. Water, Suite 10 1980 Ft. from West Line of

Wichita, KS 67202 the SW (Qtr.) SEC 1 TWP29S RGE16 (W).

PLUGGING CONTRACTOR CONTRACTOR ADDRESS

WELL PLAT

(Office Use Only)

Grid for well plat with 4 columns and 4 rows.

KCC

KGS

SWD/REP _____

PLG. _____

TOTAL DEPTH 4730' PBTD

SPUD DATE 4/8/83 DATE COMPLETED 4/12/83

ELEV: GR 2042' DF KB 2047'

DRILLED WITH ~~SCARPER~~ (ROTARY) ~~SCARPER~~ TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented Prev. set DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T


Jerry Hoggatt, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Jerry Hoggatt
Jerry Hoggatt (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 27th day of September

19 83



Janet L. Pierce
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: 6-16-85

** The person who can be reached by phone regarding any questions concerning this information.

*** IF HOLE IS PLUGGED A THIRD COPY IS NEEDED. FOR INJECTION OR DISPOSAL FOUR COPIES ARE NEEDED.

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
<p>✓ Check if no Drill Stem Tests Run.</p> <p>Washed down to R.T.D.</p>			4730' 4730'		

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE - set by previous operator							
PRODUCTION	7-7/8"	5-1/2"	15-1/2	4715'	RFC 50/50 Poz.	25 125	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A			2	4" SSB II	4634'-4642'
TUBING RECORD			2	"	4643'-4647'
Size 2-3/8" x 4.7#	Setting depth 4675'	Packer set at None	2	"	4607'-4611' 4621'-4627'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gal. MSR 100 (15%) w/22 perf balls; 5802 CCF Nitrogen frac; 250 gal. acid; 750 gal HCL (28%); refrac nitrogen frac.	4634'-4642'
crosslink jel frac	4643'-4647'
1000 gal. MSR 100 (15%) w/24 perf balls; 6065 CCF Nitrogen frac; 1500 gal. HCL (15%)	4607'-4611' 4621'-4627'
Date of first production non-commercial (Temp. Abd.)	Producing method (flowing, pumping, gas lift, etc.) Gravity
Estimated Production -I.P.	Oil bbls. Gas MCF. Water % Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Perforations