

SIDE ONE

Compt. \_\_\_\_\_

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6724 EXPIRATION DATE 6/30/83

OPERATOR Cinco Exploration Company API NO. 15-097-20922-0000

ADDRESS P.O. Box 3723 COUNTY Kiowa

Victoria, Texas 77903 FIELD Wildcat PYLE, N.E.

\*\* CONTACT PERSON Melvin Klotzman PROD. FORMATION Miss.

PHONE (512) 573-2416

PURCHASER Koch Oil Company LEASE Freda Dunbar

ADDRESS Box 2256 WELL NO. 5

Wichita, Kansas 67201 WELL LOCATION C SW NE

DRILLING Eagle Drilling, Inc. 1980 Ft. from north Line and

CONTRACTOR CONTRACTOR ADDRESS P.O. Box 8609 1980 Ft. from east Line of

Wichita, Kansas 67208 the NE (Qtr.) SEC 1 TWP 29 RGE 16W.

PLUGGING CONTRACTOR ADDRESS

WELL PLAT (Office Use Only)

KCC  KGS

SWD/REP \_\_\_\_\_ PLG. \_\_\_\_\_

TOTAL DEPTH 4765 PBD 4740

SPUD DATE 11/23/82 DATE COMPLETED 1-14-83

ELEV: GR 2055 DF 2065 KB 2068

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 445 DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

MELVIN KLOTZMAN, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

MELVIN KLOTZMAN - (Name) Petroleum Consultant

SUBSCRIBED AND SWORN TO BEFORE ME this 15th day of February, 1983.

19 83.

Doris Davenport (NOTARY PUBLIC)

MY COMMISSION EXPIRES: 12-07-84

RECEIVED DORIS DAVENPORT STATE CORRELATOR Public, Victoria County, Texas FEB 17 1983

\*\* The person who can be reached by phone regarding any questions concerning this information..

CONSERVATION DIVISION Wichita, Kansas

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 211108

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.				
Drillers Log				
Sand & red beds	0	255	Stark	4392
Red beds & clay	255	467	Hushpuckney	4432
Red beds	467	1025	Base/Kansas	4470
Red bed & shale	1025	1625	Fort Scott	4598
Shale & shells	1625	2130	Cherokee	4612
Shale & Lime	2130	4180	Miss. Congl.	4644
Lime & Shale	4180	4600	Miss.	4650
Lime	4600	4765	Kinderhook Sh	4690
			Kinderhook Lm	4692
			Kinderhook chert	4728
			Viola	4760
			Ran Dual Induction w/GR from 4765 to 446. Triple Combo from 4765 to 3700.	

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/2	8 5/8	24	445	Lite Wt. Class H.	175 100	3% CaCl <sub>2</sub> 2% gel + 3% CaCl <sub>2</sub>
Production	7 7/8	4 1/2	10.5	4765	Lite Wt. Class H.	50 100	5 lb/sk gilsonite .9 gal/sk Latex

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	3 1/8" Csg. gun	4668-4688

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	4713	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2000 gal. 15% HCl + N.E. + Clay stabilizer. 500 SCF of N <sub>2</sub> /bbl	4668-88
281 bbl. w/25,000 lbs. 20/40 sand & 5000 lbs. 10/20 sand and 715,000 SCF of N <sub>2</sub> .	

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity			
01/14/83	Pumping	33.8			
Estimated Production - I.P.	Oil bbls.	Gas Negligible	Water % 50	Gas-oil ratio 4	CFPB N/A
Disposition of gas (vented, used on lease or sold)	Perforations				
N/A	4668-88 GR				

P. O. Box 3723  
Victoria, Texas 77903  
Office: 512-573-2416 (24 Hours)  
Residence: 512-575 5053

Out of State WATS  
800-531-3640  
Houston Phone  
713-228-4058  
Texas WATS  
800-242-0085

**MELVIN KLOTZMAN**  
**PETROLEUM CONSULTANT, INC.**  
REGISTERED ENGINEER

February 15, 1984

Kansas Corporation Commission  
200 Colorado Derby Building  
Wichita, Kansas 67202

RE: CINCO ENERGY COMPANY  
Operator No.: 8819  
Kansas Producing Wells

Gentlemen:

Effective March 1, 1984 the wells listed below by company in Kansas will have an operator name change. These wells as of the effective date above will be operated by CINCO ENERGY COMPANY, 3935 Hartsdale, Houston, Texas 77063, the field office is Melvin Klotzman, Petroleum Consultant, Inc., P. O. Box 3723, Victoria, Texas 77903.

CINCO EXPLORATION COMPANY

<u>WELL NAME &amp; NO.</u>	<u>API NUMBER</u>	<u>COUNTY</u>	<u>LOCATION</u>	<u>SECTION</u>
Endicott #A-1	15-095-21,251	Kingman County, KS	C NW SE	23-27-6W
Dunbar #3	15-093-20,899	Kiowa County, KS	NE NE NE	1-29-16W
* Dunbar #5	15-097-20,922	Kiowa County, KS	C SW NE	1-29-16W
Machesney #1-A	15-097-20,554	Kiowa County, KS	SE SE	36-28-1
Machesney #2	15-097-20,984	Kiowa County, KS	SE SE	36-28-16W
Pyle #A-1	15-097-20,915	Kiowa County, KS	NE	34-27-19W
Pyle #B-1	15-097-20,924	Kiowa County, KS	NE NE NE	3-2S-17W
Vieux #1	15-097-20,836	Kiowa County, KS	SE SW SE	30-28S-18W
Miller "B" #1	15-097-20,920	Kiowa County, KS	C SE SW	3-28S-19W
Doggett #2	15-047-20,761	Edwards County, KS	C SW SE SE	24-26-16W
Parkin #1	15-097-20,935	Kiowa County, KS	C NW/4 SE/4	26-29-18W
Lubbers #1	15-155-20,741	Reno County, KS	C NW SW	16-26-8W
Brooks #1	15-155-20,776	Reno County, KS	C NE SW	17-26S-8W
Zigler #1	15-179-20,656	Sheridan County, KS	SE SW	17-10-28
Hartman #1	15-063-20,653	Gove County, KS	C NW W	5-11S-28W

RECEIVED  
STATE CORPORATION COMMISSION

FEB 21 1984

CONSERVATION DIVISION  
Wichita, Kansas

Kansas Corporation Commission  
RE: Cinco Energy Company  
Operator Name Change  
February 16, 1984  
Page - 2 -

HOUSTON HYDROLANCE INTERNATIONAL, INC.

<u>WELL NAME &amp; NO.</u>	<u>API NUMBER</u>	<u>COUNTY</u>	<u>LOCATION</u>	<u>SECTION</u>
Horinek #1	15-153-20,983	Rawlins County, KS	NW NW SW	3-1S-33W
Horinek #2	15-153-20,509	Rawlins County, KS	SW NW SW	3-1-33W
Aloise #1	15-153-20,510	Rawlins County, KS	SE NE SE	3-1-33W
Frickey #1	15-039-20,692	Decatur County, KS	C NE SW	29-2-28W
Ufford #1	15-039-20,694	Decatur County, KS	C NE SE	10-3S-29W
A & W Farms #1	15-151-21,291	Pratt County, KS	NE NW	8-28-15W
Macfee #1	15-039-20,688	Decatur County, KS	NE SE	3-2-27W
Macfee #2	15-039-20,695	Decatur County, KS	SE NW SE	3-25-27W

If there is any further information or forms required to complete this please call.

Yours very truly,



Melvin Klotzman  
Petroleum Consultant for  
CINCO ENERGY COMPANY

MK/kk

cc: Cinco Energy Company - Houston & Amarillo, Texas