

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER #15-151-20,747-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549

ADDRESS P. O. Box 351 PHONE # (316) 624-6253

LEASE (FARM) Cross "A" WELL NO. 1 WELL LOCATION 990' FSL & FEL COUNTY Pratt

SEC. 31 TWP. 29S RGE. 11E (E) or (W) TOTAL DEPTH 2855 PLUG BACK TD 2813

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 447 CEMENTED WITH 400 SACKS

CASING SIZE 4 1/2 SET AT 2851 CEMENTED WITH 150 SACKS

PERFORATED AT 2748-88

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 1 sx hulls & 10 sx Class H cmt 2788-2688, load hole w/mud & hulls. Shoot off csg @ FP. Spot 50 sx Class H cmt 525-375, mud & hulls 375-40. Spot 10 sx cmt 40-0, cut off 8 5/8" 3' below GL. Cap well.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal; KS 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547

ADDRESS P. O. Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1990
CONSERVATION DIVISION
Wichita, Kansas

SIGNED: M. L. Pease
(Operator or Agent) M. L. Pease
Division Production Mgr.

DATE: 4/5/90

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
202 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 18, 1990

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905

Coss "A" #1
990'FSL-990'FEL 31-29-11W
Pratt County, KS
API No. 15-151-20,747

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801

2600

CROSS "A" NO. 1
Sec. 31-29S-1W
Pratt County Kansas

2700

NEUTRON

GAMMA RAY

2800

CONSERVATION DIVISION
Wichita, Kansas

APR 10 1998

ONE MINUTE
INTERVAL MARKER

GUARD

WEIGHT INDICATOR

