

15-097-20914-0660

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 6 TWP. 28S RGE. 19 E/W
Location as in quarters or footage from lines:
C SW NE

Lease Owner Cinco Exploration Co.
Lease Name Glenn L. Harris Well No. 1
Office Address P.O. Box 3723 Victoria, TX 77903
Character of Well (Completed as Oil, Gas or Dry Hole): Dry
Date Well Completed 10-31-82
Application for plugging filed 10-31-82
Plugging commenced 10-31-82
Plugging completed 10-31-82
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	380	8 5/8"	373'	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

1st Plug	60 sacks @ 1080'
2nd Plug	40 sacks @ 430'
3rd Plug	10 sacks @ 40' w/ solid bridge
Rat Hole	10 sacks
Mouse Hole	10 sacks

Plugged w/130 sacks 50/50 Diamix F, 6% A-7, 4% BJ Gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Co.
105 S. Broadway, Suite 640 Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

David G. Leben (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) David G. Leben
105 S. Broadway, Suite 640
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 82

My Commission expires: 08-05-86

Arlene E. Schroer
Arlene E. Schroer Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1982

CONSERVATION DIVISION
Wichita Kansas

ARLENE E. SCHRGER
STATE NOTARY PUBLIC
SEGGWICK COUNTY, KS.
MY APPT. EXP 8-5-86

15-097-26914-0000

OPERATOR Cinco Exploration Co. LEASE NAME Glenn L. Harris SEC. 6 TWP. 28S RGE. 19W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DRILLER'S LOG				
Surface & Shale	0	380		
Sand & Shale	380	1599		
Shale	1599	1892		
Shale & Lime Streaks	1892	2363		
Shale	2363	2521		
Shale & Lime	2521	4528		
Lime	4528	4580		
Lime & Shale	4580	4680		
Lime	4680	4890		
Lime & Shale	4890	4950		
Rotary Total Depth		4950'		