

WELL PLUGGING RECORD

15-097-26780-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Kiowa SEC. 2 TWP. 28S RGE. 19W E/W
 Location as in quarters or footage from lines:
SE NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner TGT Petroleum
 Lease Name NAN Well No. 2
 Office Address 209 W. William, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed July 15, 1981
 Application for plugging filed July 15, 1981
 Plugging commenced July 15, 1981
 Plugging completed July 15, 1981
 Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well _____
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4630'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 920' with 50 sx.
Set 2nd plug @ 700' with 40 sx.
Set 3rd plug @ 40' with 10 sx.
10 sx. in rathole, 5 sx. in water well.
Plug was down @ 2:30 p.m., 7/15/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Cntr., Wichita, KS
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 81

My Commission expires 7-13-85

Elizabeth G. Terry
 Elizabeth G. Terry Notary Public.



RECEIVED
 STATE CORPORATION COMMISSION

7-29-81
 CONSERVATION DIVISION
 Wichita, Kansas

CONTRACTORS WELL LOG

15-097-20780-0000

OPERATOR: TGT Petroleum
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: NAN #2
 LOCATION: SE NW, Section 2-28S-19W
 Kiowa County, Kansas
 SPUD DATE: 6/25/81
 COMPLETION DATE: 7/15/81

0	161	Red beds
161	720	Red Bed & Sand
720	940	Shale
940	1579	Red beds & Shale
1579	4390	Lime & Shale
4390	4420	Lime
4420	4568	Lime & Shale
4568	4613	Lime
4613	4630	Lime & Shale
	4639	Rotary Total Depth

Spud hole @ 2:30 p.m., 6/25/81. Drilled 720' of a 12 1/4" hole. Ran 17 joints of 8.5/8" 24# casing set @ 714.65' with 400 sx. of Halliburton Lite, 3% c.c., and 100 sx. of Class A, 3% c.c., 2% Gel. Plug was down @ 4:15 a.m., 6/26/81.

4630' TD. Set 1st plug @ 920' with 50 sx. Set 2nd plug @ 700' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 10 sx. in Rathole, 2 sx. in the water well, 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 2:30 p.m., 7/15/81.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the NAN #2, SE NW, Section 2-28S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of July, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION

JUL 29 1981

CONSERVATION DIVISION
 Wichita, Kansas

