

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ford SEC. 33 TWP. 29S RGE. 24 EXW
Location as in quarters or footage from lines:
SE/4 SE/4 SE/4 (330' fSL and 330' fEL)

Lease Owner The Pitco Company
 Lease Name Moore Well No. 1-33
 Office Address The Pitco Company, 1790 One Williams Center, Tulsa, OK
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole 74172
 Date Well Completed Dry Hole
 Application for plugging filed Verbal Request - Rig on Hole
 Plugging commenced 12-19-82
 Plugging completed 12-20-82
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Pau Luthi
Producing formation Dry Hole Depth to top _____ bottom T.D. 5530

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Mississippi (DST)	Water	5305	5495	8 5/8	674'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. All cement 50/50 POZ containing 2% gel and 3% calcium chloride. All mud in hole had viscosity of 70 seconds funnel. Set 35 sacks plug from 1376 feet to 1480 feet. Set 35 sacks plug from 616 feet to 720 feet. Set 10 sacks plug from 10 feet to 40 feet with bridge plug at 40 feet. Filled rathole with 10 sacks plug. All plugs set with drillpipe. Cut casing off 3 feet below ground level. Welded plate on casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Haliburton - Pitco plugged with rig on location.

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Bruce D. Locke (~~employee of owner~~ ~~owner~~ ~~operator~~ or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce D. Locke
1790 One Williams Center, Tulsa, OK
(Address) 74172

SUBSCRIBED AND SWORN TO before me this 27th day of December 19 82

My Commission expires: Sept. 14, 1985

Donna S. Johnson
STATE CORPORATION COMMISSION
Notary Public.
DEC 28 1982

CONSERVATION DIVISION
Wichita, Kansas

