

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Ford SEC. 32 TWP. 29S RGE. 24 ~~XX~~W
 Location as in quarters or footage from lines:
100' E C SE NW

	X		

Lease Owner CHAMPLIN PETROLEUM COMPANY
 Lease Name Templeman "A" Well No. 1
 Office Address 6441 N.W. Grand, Suite 300, Okla. City, OK 73116
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed February 22, 1983
 Application for plugging filed June 23, 1983
 Plugging commenced June 28, 1983
 Plugging completed June 30, 1983
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant/Bob Tarbutton
 Producing formation _____ Depth to top _____ bottom T.D. 5500'
 Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1236'	None
				5-1/2"	5499'	3517'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Set CIBP @ 5280' w/4 sx cement. Pulled 160,000#
on 5-1/2" casing, showed free @ 3500'. Shot @ 3500'. Laid down 800' 5-1/2" 14# casing.
Pulled 5-1/2" casing 2700-600'. Unit broke down. Set 50 sx cement plug 1325-1225'.
Set 15 sx plug 600-500'. Finished pulling casing. Cement plug from 10-40' in 8-5/8"
casing. Cut off 8-5/8" 3' below ground level. Welded on plate. Recovered 3517' OA.
Well is P&A.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Sargent Casing Pulling

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.
J. W. MEYERS (employee of owner) or ~~(owner)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.



(Signature) [Signature]
6441 NW Grand, #300, Okla. City, OK
 (Address) 73116

SUBSCRIBED AND SWORN TO before me this 6th day of July, 19 83

[Signature]
 RECEIVED Notary Public.
 STATE CORPORATION COMMISSION

My Commission expires: 10-8-83

JUL 07 1983
 CONSERVATION DIVISION
 Wichita, Kansas