

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-057-20340-0000

LEASE NAME Dufford "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 29S RGE. 24 ~~XX~~ or (W)

COUNTY Ford

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 100 S. Main, Suite 505 Wichita, KS 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Date Well Completed 10-14-83

Character of Well Gas

Plugging Commenced 11-16-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-16-00

The plugging proposal was approved on November 16, 2000 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Morrow Depth to Top 5251 Bottom 5293 T.D. 5450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		0		8 5/8	612	None
		0		4 1/2	5445	None

DEC 6 2000

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed and pumped 200# of cottonseed hulls in fresh water. Mixed and pumped 25 sx. 60/40 Poz 6% gel w/ 100# of hulls. Followed w/ 24 sks Gel Spacer. Followed w/ 125 sx. 60/40 Poz 6% gel. with 100 sx. mixed pressure at 50# with 125 sx. mixed pressure at 708# and held. Shut well in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A

Address N. Hwy 281, P.O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) 100 S. Main, #505 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5th day of December, 192000



Karen A. Mans McGee
Notary Public

My Commission Expires: 6-23-04

Well file

Schlumberger

DUAL INDUCTION SFL LOG W/GR

CSU Field Log

COMPANY: PICKRELL DRILLING COMPANY

WELL: DUFFORD 'A' #2

NOTE: ALL OPEN HOLE LOG

FIELD: N.E. MINNEOLA

COUNTY: FORD

STATE: KANSAS

NATION: USA

LOCATION: ~~NW NE SW~~ SESENE

MEASUREMENTS ARE

7 FEET HIGH.

SEC: 3432

TWP: 29S

RGE: 24 W

PERMANENT DATUM: GROUND LEVEL ELEVATIONS-

ELEV. OF PERM. DATUM: 2570

KB: 2573

LOG MEASURED FROM: K.B.

DF: 2573

5.0' ABOVE PERM. DATUM

GL: 2570

DRLG. MEASURED FROM: KELLY BUSHING

DATE: 7 OCT 1983

RUN NO: 1

DEPTH-DRILLER: 5450.0'

DEPTH-LOGGER: 5438.0'

BTM. LOG INTERVAL: 5432.0'

TOP LOG INTERVAL: 600.0'

CASING-DRILLER: 612'

CASING-LOGGER: 612'

CASING: 8 5/8

WEIGHT: 24.00 LB/F

BIT SIZE: 12 1/4" 7 7/8"

DEPTH: 612' 5450'

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 2000

CONSERVATION DIVISION
Wichita, Kansas