

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-057-20375-0000

API NUMBER \_\_\_\_\_

LEASE NAME Sheldor

WELL NUMBER #1 \_\_\_\_\_

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 31 TWP. 29S RGE. 24W (E) or (W)

COUNTY Ford

Date Well Completed 5/29/84

Plugging Commenced 4/6/89

Plugging Completed 4/12/89

LEASE OPERATOR Lee Banks

ADDRESS 200 W. Douglas #550  
Wichita, KS 67202

PHONE#(316) 267-0783 OPERATORS LICENSE NO. 5152

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8.5/8	602	none
				4 1/2	5400	2777

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged bottom with sand to 5240', dumped 4 sacks cement, shot @4025',  
3730', 3505', 3320', 3230', 3035', 2915', 2777', pulled 68 joints,  
plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel,  
100# hulls, 125 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. \_\_\_\_\_

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Banks

STATE OF Kansas COUNTY OF Rice, ss. \_\_\_\_\_

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 89

James Hoover  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
4-19-89  
APR 19 1989