

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ford SEC. 23 TWP. 29S RGE. 24W E/W
Location as in quarters or footage from lines:
NW/4, 2173 FNL - 2173 FWL

Lease Owner Ladd Petroleum
Lease Name Cummings Well No. 1
Office Address P.O. Box 2848, Tulsa, Oklahoma 74101
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole (had to skid rig)
Date Well Completed 1/21/83
Application for plugging filed 2/24/83
Plugging commenced 1/21/83
Plugging completed 1/21/83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Permission was obtained

Name of Conservation Agent who supervised plugging of this well Paul Luthi, Dodge City, Ks.

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	1351	24	32Jts. K-55	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

50 sks cement at 570', 10 sks cement & wooden plug
at 40', 10 sks cement rathole and 10 sks cement
mousehole. Cement 50-50 poz, 2% gel, 2% CC

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton, Liberal, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Mary Kay Oeding (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Mary Kay Oeding
453 S. Webb Rd., P.O. Box 18611
Wichita (Address) Kansas

SUBSCRIBED AND SWORN TO before me this 24th day of February, 19 83

My Commission expires:

 KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 3-20-83

Kathleen G. Quinn RECEIVED
Notary Public.
STATE CORPORATION COMMISSION

FEB 25 1983

CONSERVATION DIVISION
Wichita, Kansas



453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15-057-20302-0000

WELL LOG

WELL NAME: Cummings #1
WELL LOCATION: NW/4, 23-29S-24W
Ford County, Kansas
COMMENCED: 1/15/83
COMPLETED: 1/21/83
CASING RECORD: 8 5/8" casing
set @ 1,351'

OPERATOR: Ladd Petroleum
CONTRACTOR: Aldebaran Drilling Co., Inc.

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
RED BED	0	1800'
RED BED/ANHYDRITE/DOLomite	1800'	2250'
LIME & SHALE	2250'	2986'

RECEIVED
STATE CORPORATION COMMISSION
FEB 25 1983
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
NW/4, Sec. 23-29S-24W, Ford County, Kansas TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.

Mary Kay Oeding
Mary Kay Oeding, Accountant

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th DAY OF February, 1983

MY APPOINTMENT EXPIRES:

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgewick County, Kansas
My Appt. Exp. 3-30-83

Kathleen G. Quinn
Kathleen G. Quinn NOTARY PUBLIC



March 16, 1983

State Corporation Commission
 Conservation Division
 200 Colorado Derby Building
 202 West 1st Street
 Wichita, Kansas 67202-1286

Attn: Tom Leiker
 Petroleum Proration Supervisor

Re: Cummings #1
 Rissler #1

I am returning your returned copies of the ACO-1 as you sent them to us. These wells were both prematurely abandoned (with proper notification and witnessing by state people) when severe drilling difficulties were encountered.

No wireline (logs) were run because of lost circulation and no geologic tops were picked because samples were destroyed during skidding of the rig to drill the Rissler #1.

No wireline was run or geologic samples even caught on the Cummings #1 since it also had severe lost circulation and had not reached a depth significant enough to collect samples. (2986').

Please forgive our failures, however, you have all the data available on these two holes.

Yours very truly,

A handwritten signature in cursive script, appearing to read "D. P. Spencer".

D. P. Spencer
 Manager of Engineering

kjp
 Attachment

RECEIVED
 STATE CORPORATION COMMISSION

MAR 18 1983

CONSERVATION DIVISION
 Wichita, Kansas