

API NUMBER 15-097-20,054-0000

LEASE NAME White

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 27 TWP. 27 RGE. 16 (E) or (W)

LEASE OPERATOR J. Mark Richardson

ADDRESS 640 Century Plaza, 111 W. Douglas, Wichita, Ks. 67202 COUNTY Kiowa

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414 Date Well Completed June 1968

Character of Well oil Plugging Commenced 1/18/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 1/19/89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kinderhook Depth to Top 4601 Bottom 4678 T.D. 4765

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	278	8 5/8	15	none
		0	4765	4 1/2	149	66

RECEIVED
 STATE CORPORATION COMMISSION
 APR 4 1989
 4-4-1989
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Set cast iron plug @ 3140 dump bail 2 sk cement, cut off and pull 2092 Ft.

66 jt 4 1/2 pump 2 sk hull - 10 gel - 50 sk 60/40 cement. 10 gel, 1 hull 120 sk
60/40 cement 650# max pron 250# ISIP plug down 12:15 1/24/89

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Greensburg Well Service License No. 5414

Address 303 E. Kansas Greensburg,

STATE OF Kansas COUNTY OF Kiowa, ss.

J. Mark Richardson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 111 W. Douglas Wichita, Ks. 67203

SUBSCRIBED AND SWORN TO before me this 31 day of March, 19 89

Kim Santella
 Notary Public

My Commission Expires: 2/22/89



GABBERT JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELLS LOG

WHITE #1
 C SW SW SECTION 27-279-16W
 KIOWA COUNTY, KANSAS

COMMENCED: MAY 21, 1968
 COMPLETED: JUNE 1, 1968

OPERATOR - J. MARK RICHARDSON

DEPTH		FORMATION	REMARKS
From	To		
0	175	SAND	
175	279	SHALE	RAN 15 JOINTS 8-5/8" CASING BET @ 278' w/230 BAGS CEMENT.
279	300	SHALE	
300	1023	SHALE AND RED BED	
1023	1058	ANHYDRITE	
1058	1240	SHALE AND SHELLS	
1240	1645	SHALE	
1645	2190	SHALE AND SHELLS	
2190	2500	LIME	
2500	4122	LIME AND SHALE	
4122	4325	LIME	
4325	4417	LIME AND SHALE	
4417	4770	LIME	
4770	TO		RAN 149 JOINTS OF 4 1/2" CASING BET @ 4765' w/150 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SW SECTION 27-279-16W, KIOWA COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THE 17TH DAY OF JUNE, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC