


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 30 Twp. 27S Rge. (E) 16 (W)  
SE NW

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner. Eason Oil Co.  
Lease Name Tuller Block 1 Well No. 1-30  
Office Address Box 18755, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 11-17-65 19\_\_\_\_  
Application for plugging approved 11-18-65 19\_\_\_\_  
Plugging commenced 11-18-65 19\_\_\_\_  
Plugging completed 12-1-65 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4780 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	244	0
				8 5/8	2400	1323
				2 7/8	4778	3030

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Shot 2 7/8" tubing at 4310, 4004, 3723, 3513, 3208 and 3025.  
Pulled 99 joints of 2 7/8". Shot 8 5/8" casing at 1325'. Pulled 41 joints. Squeezed 13 3/8" surface with 20 sacks gel, and 200 sacks cement. Well was kept full of heavy mud during above operations.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 29 1965

CONSERVATION DIVISION  
Wichita, Kansas

12-29-1965

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gayle E. Toland  
Address Box 94336, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
F. W. Akright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Akright  
December 27, 1965 Vice President  
(Address)

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of December, 1965

My commission expires SEPTEMBER 11, 1966 Notary Public.



# WELL LOG

COMPANY Eason Oil Company

SEC. 30 T. 27S R. 16W

FARM Tuller

NO. 1

LOC. SE NW


TOTAL DEPTH 4780'

COUNTY Kiowa

COMM. 9-20-65

COMP. 10-9-65

CONTRACTOR Garvey Drilling Company



CASING 13 3/8" @ 244' w/250 sx

8 5/8" @ 2400' w/100 sx

ELEVATION 2126' DF

PRODUCTION Capped Surface csg.  
No plug in hole.

FIGURES INDICATE BOTTOM OF FORMATIONS

- 120' Sand
- 150' Sand and Shale
- 246' Shale
- 300' Shale and Shells
- 1045' Red Bed and Shale
- 1060' Anhydrite
- 1190' Red Bed and Shale
- 1265' Shale and Shells
- 1430' Shale w/Lime Streaks
- 1870' Shale w/Shells
- 2125' Shale, Shells and Salt
- 2195' Shale and Salt
- 2275' Shale with Lime
- 2297' Shale and Lime
- 2350' Anhydrite
- 2400' Lime and Shale
- 2535' Lime with Shale
- 2638' Lime
- 2923' Shale with Lime
- 3235' Lime and Chalk
- 3289' Lime with Chalk and Shale
- 3631' Lime and Shale
- 3700' Lime with Shale and Chalk Streaks
- 3890' Lime and Shale
- 3950' Shale and Lime
- 4180' Lime and Shale
- 4477' Lime
- 4660' Lime with Shale
- 4702' Shale, Lime, and Chert
- 4754' Lime with Chert
- 4780' Lime
- 4780' RTD

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1965

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas

County of Barton

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Tuller #1 well.

*Sam N. Stephens*

Subscribed and sworn to before me this 22nd day of October 19 65

My Commission Expires: May 28, 1969

*Richard H. Dunder*  
NOTARY PUBLIC