


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kiowa County, Sec. 31 Twp. 28 Rge. 16 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner M. P. & B. D. Gilbert  
Lease Name Smitherman Well No. #1  
Office Address 220 W. O. Garvey Bldg.; Wichita, Ks. 67202  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed October 1970  
Application for plugging approved October 1970  
Plugging commenced October 29 1970  
Plugging completed November 2 1970  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280	None
				5 1/2	4750	2906

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-10-1970

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

October 29, 1970 Plugged off bottom. Dumped sand to 4000'.  
Mixed and dumped 5 sx of cement to 3960'.

November 2, 1970 Plugged off top. Set 10' rock bridge at  
260'. Filled 8 5/8" surface casing from  
260' to base of cellar with 4 yards of  
3000 lb. P.S.I. ready mix concrete.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Russ Casing Pulling, Inc.  
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Mark Richardson  
J. Mark Richardson  
200 OW Garvey Bldg., Wichita, Kan.  
(Address)

Subscribed and sworn to before me this 10th day of Nov., 1970

November 4, 1973

Mary Ann Isbell  
Mary Ann Isbell Notary Public.



JUN 14 1969

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

31-27-16W

SMITHERMAN #1  
C NE SE Section 31-27S-16W  
Kiowa County, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

*sp. of  
the name*

Commenced: November 25, 1968  
Completed: December 16, 1968

OPERATOR - B. D. and M. P. Gilbert

DEPTH		FORMATION	REMARKS
From	To		
0	145	Surface clay and sand	
145	280	Shale	Ran 7 joints 8-5/8" casing, set @ 280' w/240 sacks cement.
280	975	Shale	
975	2158	Shale and shells	
2158	4100	Lime and shale	
4100	4660	Lime	
4660	4700	Lime and chert	
4700	4789	Lime	
4789	4800	Lime and chert	
4800	TD		Ran 146 joints 5-1/2" casing, set @ 4798' w/150 sacks cement.

*low permeability foot - "Kudor hook"*

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SE Section 31-27S-16W, Kiowa County, Kansas, to the best of my knowledge and belief.

*E. E. Hall*  
E. E. HALL


STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 17 day of December, 1968, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Barbara J. Layton*  
Barbara J. Layton, Notary Public

My Commission Expires Feb. 1, 1972.



~~B. E.~~  
J. A. H. H.  
G. F. M.

DEC 26 1968

*(We have 3 copies  
+ drilling records)*

*DM*