

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-097-30135-0000

API NUMBER N/A

LEASE NAME WOODARD

WELL NUMBER #1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 32 TWP. 27 RGE. 16W (E) or (W)

COUNTY KIOWA

Date Well Completed 2/19/65

Plugging Commenced 1/1/96

Plugging Completed 2/14/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR J. MARK RICHARDSON

ADDRESS 155 N MARKET #840 WICHITA KS 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/20/95 (date)

by STEVE PENDLTON (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? YES

Producing Formation KINDERHOOK Depth to Top 4590 Bottom 4660 T.D. 5690

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

3-21-1996

Formation	Content	From	To	Size	Put In	Pulled out
KINDERHOOK	OIL	0	282	8 5/8	282	0
		0	4692	4 1/2	4692	2352

KANSAS RECEIVED
 1996 MAR 21 AM 10:54

Describe in detail the manner in which the well was plugged, indicating where the mud plug was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. sand off well to 4500', dump bail, 4 sk cement, take free point, cut 4 1/2 cs.; 2370 pull & lay down same, set to plug with 300# hulls, 10 sk gel, 50 sk cement, 10 sk gel, 100# hulls, 150 sk 60/70 pox 6% gel, 250# max press ISIP 100#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. 31201

Address 303 E KANSAS, GREENSBURG, KS. 67054

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. MARK RICHARDSON

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 155 N MARKET #840 WICHITA KS 67202

SUBSCRIBED AND SWORN TO before me this 8TH day of MARCH, 19 96

KIM DANTELLAN
 State of Kansas
 My Appt. Exp. _____
 My Commission Expires: _____

2/22/2000

[Signature]
 Notary Public