

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 32 TWP. 27S RGE. 16 ~~EW~~W
Location as in quarters or footage from lines:
C-SW=SE

		*	

Locate Well
correctly on above
Section Platt.

Lease Owner Koch Oil
Lease Name Woodward Well No. 2
Office Address Box 2256 Wichita, Kansas 67201
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 5-28-66
Application for plugging filed March, 1983
Plugging commenced March 8, 1983
Plugging completed March 10, 1983
Reason for abandonment of well or producing formation

not economical to produce
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well agent on location
Producing formation Kinderhook Depth to top 4660 bottom 4684 T. Plug back TD 4721'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>4 1/2 casing</u>		<u>0</u>		<u>4 1/2</u>		<u>2420'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plug back TD 4721'. To 4600' with 121 ft. of sand, 4 sx. cement on top
of sand, perms. from 4660 to 64'. 4668 to 84'. Shot off casing at 2420'. Had
266' of surface pipe, did not plug surface pipe. Plugged with 2 sx. hulls, 14 sx.
gel, 70 sx, 50/50 Poz mis, 10 sx. gel, dropped plug, 130 sx. cement 50/50 poz mix.
Dowell did cement work.

RECEIVED
STATE CORPORATION COMMISSION


MAR 21 1983

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pratt Well Service, Inc.

CONSERVATION DIVISION
Wichita, Kansas

3-21-1983

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Baird (employee of owner) or (~~owner~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Baird
Box 847 Pratt, Kansas 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 83

Charlene M. Dudrey
Notary Public.

My Commission expires: 9/10/86