


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD,

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 32 Twp. 27 Rge. 16 ~~E~~/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
S/2 SE NW
Lease Owner F & M Oil Co., Inc.
Lease Name Fankhauser Well No. 1
Office Address 422 Union Center, Wichita, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed October 11 19 81
Application for plugging filed October 11 19 81
Application for plugging approved October 11 19 81
Plugging commenced October 11 19 81
Plugging completed October 11 19 81
Reason for abandonment of well or producing formation

D & A
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luth, Minneola, Ks.
Producing formation Depth to top Bottom Total Depth of Well 4785
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	286	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 800 ft. 40 sx
- 270 ft. 35 sx
- 40 ft. 10 sx
- 50/50 poz
- 2% gel; 3% cc
- 5 sx rathole
- 10 sx water well

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
William Nelson (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William Nelson
P.O. Drawer 1609, Gt. Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 19 81

JEWELRY SHEWBART
Notary Public
My commission expires April 14, 1982

Jewelry Shewbart
Notary Public.

DRILLERS' WELL LOG

OPERATOR: F & M Oil Co., Inc.
422 Union Center, Wichita, Kansas 67202

WELL: Fankhauser #1 API # 15- 097- 20,797

LOCATION: S/2 SE NW
Sec 32 -T 27 S-R16W

COMMENCED: October 2, 1981 COMPLETED: October 11, 1981

ELEVATION: GL: 2109 DF: KB: 2120 TOTAL DEPTH: 4785

CASING: Surface: 8 5/8"; 20 #; set at 286 feet;
Cemented with 175 sacks Common cement; 3% cc; 2% gel

Production: ; #; set at feet;
Cemented with sacks cement;

DEPTH:	FORMATION	FORMATION TOPS		
0 - 1740	Sand, Shale	Heebner	3950	-1830
1740 - 2312	Shale	Douglas	3975	-1855
2312 - 3950	Lime, Shale	Brown Lime	4112	-1992
3950 - 3954	Shale	Lansing	4127	-2007
3954 - 3975	Lime, Shale	Marmaton	4499	-2379
3975 - 4112	Shale	Cherokee	4619	-2499
4112 - 4127	Lime, Shale	Mississippian	4672	-2552
4127 - 4499	Lime	Kind Sand	4695	-2575
4499 - 4672	Sand	Viola	4757	-2637
4672 - 4695	Chert, Lime	LTD	4785	
4695 - 4757	Sand	RTD	4785	
4757 - 4785	Lime			
4785	LTD			
4785	RTD			

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1981
CONSERVATION DIVISION
Wichita, Kansas

ACKNOWLEDGEMENT

STATE OF KANSAS, COUNTY OF BARTON, ss:

Before me, the undersigned, a Notary Public, within and for said county and state, on this 12th day of October, 1981, personally appeared William Nelson to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 12th day of October, 1981.

My Appointment Expires: **BEVERLY SHEWBART**
Barton County, Kansas

April 14, 1982

William Nelson
Beverly Shewbart
Notary Public