

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-20,584-0000

LEASE NAME FANKHOUSER C

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

160 Ft. from E Section Line

SEC. 22 TWP. 27 RGE. 16W (E) or (W)

LEASE OPERATOR J. MARK RICHARDSON

COUNTY KIOWA

ADDRESS 2843 KEYWEST CT WICHITA KS 67204

Date Well Completed 12/79

PHONE# (316) 838-4242 OPERATORS LICENSE NO. 5414

Plugging Commenced 7/20/00

Character of Well GAS

Plugging Completed 7/26/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/30/00 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation KINDERHOOK SAND Depth to Top 4621 Bottom 4625 T.D. 4640-2548

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
GAS		0	390	8 5/8	390	0
		0	4631	4 1/2	4631	2315

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
KLIMA pull & lay down in singles 184-3/4 rods. Pull and log down 147 jts of 2 3/8 TB, drop sand to cover perms. 80 bls water. Top of sand 4300', dump bail 4 sks cement on sand, dig out cellar. Pull slips, work pipe, take free point, load cs w/water truck, cut 4 1/2 cs @ 2315', lay down 57 jts 4 1/2 10 sks gel, 50 sks cement, 10 sks gel, 100lbs hulls, 8 5/8 plug, 150 sk cem. 450#
 (If additional description is necessary, use BACK of this form.)
 maximum pressure, 150# IISIP. Cement 60/40 6% gel.

Name of Plugging Contractor Klima Well Service License No. RECEIVED

Address P.O. Box 386, Claflin KS STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. Mark Richardson AUG 24 2000

STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION
 Wichita, Kansas

J. Mark Richardson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. Mark Richardson

(Address) 2843 Keywest Ct

SUBSCRIBED AND SWORN TO before me this 21st day of August, 2000

Wichita KS 67204
 KIM SANTELLAN
 State of Kansas
 Notary Public

My Commission Expires: 3-13-04

Kim Santella
 (Signature)