

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20433-0000

LEASE NAME Davis

WELL NUMBER 2-18

         Ft. from S Section Line

         Ft. from E Section Line  
SE Sw

SEC. 18 TWP. 27 RGE. 16W(E) or (W)

COUNTY Kiowa

Date Well Completed 12-22-87

Plugging Commenced 10-13-87

Plugging Completed 11-20-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR K & K Oil

ADDRESS P.O. Box 176  
Chase, Kansas 67524

PHONE#(316) 938-2457 OPERATORS LICENSE NO. 9339

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	403'	none
				4-1/2"	4719'	2436'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped bottom with 1 sack hulls and 20 sacks common to 4360'. Shot pipe @3718', 2505', 3312', 3188', 3002', 2808', 2604', 2436', pulled a total of 77 joints of 4-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 3rd. day of December, 1987

Gene Hoover  
Notary Public

My Commission Expires:         



RECEIVED  
STATE CORPORATION COMMISSION  
DEC 7 1987  
12-7-1987  
CONSERVATION DIVISION CP-4  
Wichita, Kansas Revised 07-86