

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-053-20,988-00-00

LEASE NAME Becker Trust

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1450 Ft. from S Section Line

3170 Ft. from E Section Line

SEC. 19 TWP. 16 RGE. 8 (E) or (W)

COUNTY Ellsworth

LEASE OPERATOR Petroleum Energy, Inc.

ADDRESS 224 E. Douglas - Suite 350, Wichita, KS 67202

PHONE# (316) 265-2661 OPERATORS LICENSE NO. 5230

Date Well Completed 3-7-86

Character of Well D&A

Plugging Commenced 3-7-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-7-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Salina, Ks.
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3295'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>260</u>	<u>0</u> <u>Putt 8-10-15</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 3281' w/35 sacks cement thru drill pipe

Next Plug: @ 490' w/50 " " " " " "

Next Plug: @ 310' w/35 " " " " " "

Top Plug: @ 40' w/1 sack Hulls & 15 sacks cement 10 sacks in Rat Hole
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 10 day of March, 1986

Doreen M. Blaque
Notary Public

My Commission Expires: 4-29-86

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1986
3-12-86
CONSERVATION DIVISION
Wichita, Kansas

15-053-20988-0000

DRILLER'S WELL LOG

DATE COMMENCED: March 2, 1986
DATE COMPLETED: March 7, 1986

Petroleum Energy, Inc.
BECKER TRUST #1
200' SW of SE NE-SW
Sec. 19, T16S, R8W
Ellsworth County, Ks.

ELEVATION: 1729 K.B.

0 - 390'	Surface Soil, Shells, Shale
390 - 398'	Anhydrite
398 - 2324'	Lime & Shale
2324 - 2358'	Lime
2358 - 2377'	Shale & Sand
2377 - 2632'	Lime
2632 - 2665'	Shale & Lime
2665 - 2750'	Shale
2750 - 2764'	Lime & Shale
2764 - 3073'	Lime
3073 - 3189'	Shale, Lime, Chert, Sand
3189 - 3237'	Chert
3237 - 3291'	Sand
3291 - 3295'	Dolomite
3295'	RTD

FORMATION DATA

Anhydrite	390'
Howard	2324'
Severy	2358'
Topeka	2377'
Heebner	2632'
Toronto	2653'
Douglas	2665'
Br. Lime	2750'
Kansas City	2764'
Base K.C.	3073'
Conglomerate	3092'
Biola	3189'
Simpson	3237'
Arbuckle	3291'
RTD	3295'

Surface Pipe: Set new
8-5/8", 20# pipe @260'
w/150-sacks 50/50 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 10 day of March 1986.

My Comm. Expires:

4-29-86

Dorothy M. Hague
Notary Public

STATE CORPORATION COMMISSION

MAR 12 1986

CONSERVATION DIVISION
Wichita, Kansas