

STATE OF KANSAS
STATE-CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15025-20669-00-08

LEASE NAME MINNEOLA UNIT

WELL NUMBER 12-2 (TEDFORD 2-10)

NOTICE: Fill out completely 4620 Ft. from S Section Line
and return to Cons. Div. 1980 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 10 TWP. 30S RGE. 25W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY CLARK

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 2/13/83

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 7/9/02

Plugging Completed 7/9/02

The plugging proposal was approved on 7/9/02 (date)

by STEVE MIDDLETON W/KCC DODGE CITY, KS.

(KCC District Agent's Name)

Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation MORROW Depth to Top 5316 Bottom 5382 TD 5500'

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	1377	8 5/8	1377	0
		production	5455	5 1/2	5455	2600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Shot @ 2600' laid csg down. Welded 8 5/8" collar on. Surface w/300# hulls, 10 sxs gel, 50 sxs cement, 10 sxs gel, 100# hulls, released plug & 150 sxs cement 60/40 pos, 6% gel. Well P&A. Witnessed & approved by Steve Middleton w/KCC Dodge City, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 19 th day of July, 2002

Notary Public - Barbara J. Dodson [Signature]

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
JUL 22 2002
KCC WICHITA
7-27-2002

[Handwritten initials]

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

RECEIVED
JUL 19 2002

Date	Invoice #
7/18/2002	9368

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

RECEIVED
JUL 22 2002
KCC WICHITA

FA 36/RK

P.O. No.	Lease	County
	Minneola 12-2	Clark

Qty	Description	Rate	Amount
17	Hours Rig Time	120.00	2,040.00T
2	Shots	150.00	300.00T
2	Sacks Cement	10.50	21.00T
	Solvent	6.00	6.00T
4.5	Hours - Welder	40.00	180.00T
1	5-1/2" Collar	45.00	45.00T
1	8-5/8" Collar	60.00	60.00T
2	Hours - Truck Move Floor	50.00	100.00T
1	Night Out of Town Expense	135.00	135.00
	6-27-02 Drove to location, Log Tech set CIBP @5270'. 1 Hour.		
	6-28-02 Set rig in on location, rigged up, welder took head apart and welded on 5-1/2" collar. 2 Hours.		
	7-1-02 Picked up cement, drove to location, dumped 2 sacks cement with bailer on top of CIBP @5270'. Set in floor and rigged up, shot pipe loose @2720', pulled 20 ft. and pipe hung up. Couldn't work loose, left on tension. 10 Hours.		
	7-2-02 Drove to location, pipe still not loose, shot @2600', layed casing down, tore down, tallied pipe and moved off.		
	7-7-02 Welder cut head off and welded 8-5/8" collar on.		
	7-9-02 Allied Cementing plugged surface with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and 150 sacks cement, 60/40 pos, 6% gel. Plugging complete.		
		Total	

Mike's Testing & Salvage Inc.

P.O. Box 467
Chase, KS 67524

Invoice

Date	Invoice #
7/18/2002	9368

Bill To
Murfin Drilling Co., Inc. 250 N. Waster, Suite 300 Wichita, Kansas 67202

RECEIVED
JUL 22 2002
KCC WICHITA

P.O. No.	Lease	County
	Minneola 12-2	Clark

Qty	Description	Rate	Amount
	7-16-02 Welder Cut 8-5/8" collar off and cut out dutchman. Sales Tax	6.30%	173.38
Total			\$3,060.38