

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-057, 20,108-0000

LEASE NAME McFadden

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 33 TWP. 29S RGE. 22 (W) (X)

COUNTY Ford

LEASE OPERATOR Plains Resources Inc.

ADDRESS 1601 NW Expressway, Okla. City, OK 73118

PHONE# (405) 842-2008 OPERATORS LICENSE NO. 05236

Date Well Completed 2-16-78

Plugging Commenced 11-20-87

Character of Well P & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-8-87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District 1

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Morrow-Mississippi Depth to Top 5265 Bottom 5416 T.D. 5416

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 DEC 9 4 1987
 12-14-87
 WICHITA, KANSAS

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|--------------------|---------|------|------|--------|--------|------------|
| Morrow-Mississippi | Dry | 0 | 281 | 8 5/8" | 281 | |
| | | | 5415 | 4 1/2" | 5415' | 2825' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Squeezed Morrow-Mississippi. Pmpd 1 sk cotton seed hulls & 20 sxs cmt 5100'. Pulled on pipe. Free pt @ 2700'. Shot pipe @ 4010, would not come loose. Shot pipe @ 2825'. POH to 1875'. Pmpd 50 sxs cmt 1875'-1775'. POH to 940'. Pumped 50 sxs cmt 940'-840'. POH to 310'. Pmpd 40 sxs cmt 310'-210'. Pumped cmt 40' to 4'. Cut off surf csg @ GL. Weld steel plate with date on. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargeants Casing Pulling Service License No. 6547

Address P. O. Box 506, Liberal, KS 67905-0506

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

William D. Arbuckle (Employee of Operator) or (XXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William D. Arbuckle

(Address) 1601 NW Expressway, Okla. City, OK 73118

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1987

Gene Cooley Goodwin
 Notary Public

My Commission Expires: 9-2-90