

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ford County, Sec. 25 Twp. 29S Rge. 21 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE SW SE


Lease Owner Imperial Oil Company  
Lease Name Seacat Well No. 1-25  
Office Address 720 Fourth Financial Center Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed 09-10 1979  
Application for plugging filed 09-10 1979  
Application for plugging approved 09-10 1979  
Plugging commenced 09-10 1979  
Plugging completed 09-10 1979  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 5400  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	612'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

50 sacks @ 660'  
10 sacks @ 40'  
5 sacks in rat hole

STATE RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Robert L. Eisel (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Eisel  
Suite 210 260 N. Rock Road Wichita, KS 67206  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1979

Sharon Winter  
Sharon Winter Notary Public.

My commission expires August 13, 1983



SCC

15-057-20143-0000

DRILLER'S LOG

Operator: Imperial Oil Company  
 Lease Name: Seacat #1-25  
 Spot Location: NE SW SE  
                   Sec. 25-29S-21W  
 County, State: Ford County, Kansas

Commenced: 08-27-79  
 Completed: 09-10-79

Surface Casing: 15 joints 8 5/8" 612' 200 sacks  
Howco light 3% cc 150 sacks regular 2% gel 3% cc  
WOC 1 hour 50 sacks regular 2% gel 3% cc  
 cement circulated

<u>FORMATION</u>	<u>DEPTH</u>
<u>Clay Sand Red Bed</u>	<u>0 - 540</u>
<u>Red Bed &amp; Shale</u>	<u>540 - 1225</u>
<u>Shale &amp; Shells</u>	<u>1225 - 2640</u>
<u>Lime &amp; Shale</u>	<u>2640 - 5025</u>
<u>Lime</u>	<u>5025 - 5400</u>
<u> </u>	<u>TD - 5400</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 17 1979  
 CONSERVATION DIVISION  
 Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

EAGLE DRILLING, INC.  
*J. G. Gould*  
 J. G. Gould

STATE OF KANSAS     )  
 COUNTY OF SEDGWICK ) ss:

Subscribed and sworn to before me this 13th day of September, 79.

My appointment expires August 13, 1983

*Sharon Winter*  
 Sharon Winter

SHARON WINTER  
 STATE NOTARY PUBLIC  
 SEDGWICK COUNTY, KS.  
 My Appt. Exp. 8/13/83  
 KANSAS