


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Ford County, Sec. 17 Twp. 29S Rge. (E) 21 (W)

Location as "NE/CNWKSWK" or footage from lines NE NW SW  
Lease Owner Morrison Drlg Co., Inc.  
Lease Name Ruddy Well No. 1  
Office Address 400 No. Main, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 22, 1955 19  
Application for plugging filed December 22, 1955 (verbal) 19  
Application for plugging approved December 22, 1955 (verbal) 19  
Plugging commenced December 23, 1955 19  
Plugging completed December 23, 1955 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 5336 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	425	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 350'.  
Set bottom plug at 350' and 1/2 sack hulls and 20 sacks cement.  
Filled with mud to 35 feet. Set plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Drilling Co. (License No. 20)  
Address 1005 East Second, Wichita, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. W. Wilson (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
400 North Main, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1955

My commission expires April 27, 1957

[Signature] Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1955

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 17 T 29 S 21 W  
BOOK PAGE 27 LINE 1

NO. 1 RUDDYWELL LOG

Location: NE NW SW, 17-29S-21W  
Ford County, Kansas

Operator: Morrison Drilling Company, Inc.  
400 North Main, El Dorado, Kansas

Contractor: Graham-Messman-Rinehart Drilling Company  
1005 East Second, Wichita, Kansas

Commenced: November 30, 1955  
Completed: December 23, 1955  
Elevation: 2408 KB (2398 GL)  
Production: D&A

Casing Record: 8 5/8" @ 425' w/250 sacks cement

## .....L O G.....

Clay-Sand	150
Clay-Sand-Red Bed	497
Red Bed-Shale	960
Shale	1343
Shale-Red Bed-Gyp	1760
Shale	2446
Shale-Lime	2777
Lime-Shale	2903
Shale-Lime	3103
Lime-Shale	3240
Shale-Lime	3383
Shale	3585
Lime-Shale	3686
Shale-Lime	4073
Lime-Shale	4442
Shale-Lime	4547
Lime	4812
Lime-Shale Streaks	4888
Lime	4906
Lime-Shale Streaks	4970
Lime	5011
Lime-Shale Streaks	5110
Lime-Shale	5146
Lime-Chert	5163
Core #1	5185
Core #2	5205
Core #3	5242
Core #4	5299
Lime	5304
Core #5	5336 R.T.D.

Sample Tops:

Toronto 3816 (-1408)  
Heebner 4280 (-1872)  
Brn Lime 4449 (-2041)  
Lansing 4458 (-2050)  
Conglomerate 5150 (-2742)  
Mississippi 5156 (-2748)

THE undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

FLUGGON  
F&M SEC 17 T 29 S 21W  
BOOK PAGE 27 LINE 1

By: J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me this  
28th day of December 1955.

Quentin L. Loria  
Notary Public

My Commission Expires: November 5, 1955