

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Ford SEC. 12 TWP. 29S RGE. 21W E/W  
Location as in quarters or footage from lines:  
C NE NW

	+		
		12	

Locate Well  
correctly on above  
Section Platt.

Lease Owner Spines Exploration, Inc.  
Lease Name Patton Well No. 1  
Office Address 530 Fourth Financial Center, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole.  
Date Well Completed May 27, 1982  
Application for plugging filed 6-2-82  
Plugging commenced 5-15-82  
Plugging completed 5-27-82  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5195'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	610'	8-5/8"	603.19'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged with 50 sacks cement at 1020';  
50 sacks cement at 660'; 10 sacks cement  
at 40'; and 10 sacks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
John D. Knightley, Agent (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
221 S. Broadway, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 1982



My Commission expires: March 12, 1983

[Signature] Notary Public.  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 1982  
CONSERVATION DIVISION  
Wichita Kansas

Spines Exploration, Inc.  
530 Fourth Financial Center  
Wichita, Kansas 67202

- Patton #1  
C NE NW Sec. 12-29S-21W  
Ford County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: May 15, 1982  
Completed: May 27, 1982

Drillers Log

---

Clay	95
Sand & Gyp	175
Shale	390
Red Bed	572
Gyp	590
Shale	613
Red Bed & Shale	1021
Anhydrite	1031
Shale	1869
Shale & Shells	2195
Shale	3130
Shale & Lime	4165
Lime & Shale	4480
Lime	4605
Lime & Shale	4815
Shale & Lime	4898
Lime	5195 RTD

15-057-20262-0000

Phone: 913-483-2627, Russell, Kansas  
 Phone: 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618.

# ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 29877

NEW

Date	5/27/82	Sec.	12	Twp.	29	Range	21	Called Out		On Location	6:00 AM	Job Start		Finish	8:30 AM	
Lease	PAISON	Well No.	#1	Location				MUNNIVILLE 4w 1 1/2s 2w	County	FORK	State	KS				

Contractor	D.R. LAUCK	
Type Job	ROTARY PLUG	
Hole Size	7 7/8'	T.D. 5195'
Csg. Size	8 5/8'	Depth 602'
Tbg. Size		Depth
Drill Pipe	4 1/2	Depth 1020'
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.		Minimum
Meas Line		Displace
Perf.		

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	SPINX'S EXPLORATION
Street	525 4th FINANCIAL CENTER
City	WICHITA State KS 67212
The above was done to satisfaction and supervision of owner agent or contractor.	

EQUIPMENT		
Pumptrk	No 105	Cementor - LARRY Helper - DUIN
Pumptrk	No	Cementor Helper
Bulktrk	116	Driver - OLLI
Bulktrk		Driver

Purchase Order No.	X
<b>CEMENT</b>	
Amount Ordered	1205x 5 5/8" 202 49600 39 CC
Consisting of	
Common	1005x 40
Poz. Mix	1005x 100
Gel.	55x 600
Chloride	35x 200
Quickset	

DEPTH of Job		
Reference:	PUMP TRUCK	360.00
	8 5/8 PLUG	10.00
	4 1/4 mi @ 100 m.	44.00
	Sub Total	
	Tax	
	Total	414.00

Handling	1285x	Sales Tax	900
Mileage	94 mi		660
	Sub Total		
	Total		

Remarks:

505x - 1020'  
 505x - 600'  
 105x - 40' W/BRIDGE  
 105x - RATHOLE

Floating Equipment

**RECEIVED**  
 STATE CORPORATION COMMISSION

1111 - 2 1982

CONSERVATION DIVISION  
 Wichita, Kansas