

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY PRATT SEC. 10 TWP. 29S RGE. 12W E/W
Location as in quarters or footage from lines:
C SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner TOM KAT LTD.
Lease Name PRATT MILLER Well No. #1
Office Address 250 N. ROCK ROAD, BOX 18611, WICHITA, KS. 67218
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed 6:45 P.M. 10-31-83
Application for plugging filed 11-3-83
Plugging commenced 4:45 P.M. 10-31-83
Plugging completed 6:45 P.M. 10-31-83
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ED KNOBLOCK - DODGE CITY
Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	8 5/8"	0	263'	J-55	6 Jts.	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Well was plugged as follows:
Plugged with 170 sks. 60-40 pos., 2% gel., 3% cc.
1st plug stated at 4659' 30 sks., 2nd plug 820' 50 sks., 3rd plug 320' 50 sks.,
4th plug at 40' solid plug 10 sks., rat hole 15 sks., mouse hole 10 sks., water well 5 sks.

(If additional description is necessary, use BACK of this sheet.)
Name of Plugging Contractor SUN OIL WELL CEMENTING, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Arnie Little ARNIE LITTLE
VICE-PRESIDENT
BOX 18611 453 S. WEBB ROAD
WICHITA (Address) KANSAS 67202

SUBSCRIBED AND SWORN TO before me this 3RD day of NOVEMBER, 19 83

Kathleen G. Quinn
KATHLEEN G. QUINN Notary Public.

My Commission expires: MARCH 20, 1987



RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1983
11-4-83
CONSERVATION DIVISION
Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

W E L L L O G



WELL NAME: PRATT MILLER #1

WELL LOCATION: C SW NW,

SEC. 10-29S-12W, PRATT CO.

COMMENCED: 8:00 A.M. 10-22-83

COMPLETED: 6:45 P.M. 10-31-83

CASING RECORD: 8 5/8" set at
263'

OPERATOR: TOM KAT LTD.

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>
Red Bed, Sand, Clay	0'	300'
Red Bed, Clay	300'	1000'
Red Bed, Shale, Lime	1000'	1300'
Shale with Lime	1300'	4180'
Kansas City/Lime, Shale	4180'	4270'
Top Mississippian	4270'	4276'
Mississippian	4276'	4416'
Viola	4416'	4440'
Viola, Simpson	4440'	4560'
Lime, Arbuckle	4560'	4699'

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1983

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

CONSERVATION DIVISION
Wichita, Kansas

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
C SW NW, SEC. 10-29S-12W, PRATT CO., KANSAS TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.
ARNIE LITTLE
VICE-PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 3RD DAY OF NOVEMBER, 1983

MY APPOINTMENT EXPIRES: MARCH 20, 1987
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 3-20-87

Kathleen G. Quinn
KATHLEEN G. QUINN
NOTARY PUBLIC