

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-151-20,983-00-00

LEASE NAME Mueller

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

NE SE NW  
 SEC. 7 TWP. 29S RGE. 12 ~~XX~~ or (W)

COUNTY Pratt

Date Well Completed         

Plugging Commenced 10-19-89

Plugging Completed 10-27-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place Wichita, Ks. 67202

PHONE#( 316 ) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached?         

Producing Formation          Depth to Top          Bottom T.D.4681

Show depth and thickness of all water, oil and gas formations. PBTD 4304

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	214	8 5/8	214	0
			4670	4 1/2"	4670	2829' 67 joints

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

OCT. 19: Cut and pulled 67 joints of 4 1/2" casing. First dumped sand to 4120' and dumped 4 sx. cement on top of that.

Oct. 27: Top hole plugging: 3 hulls, 10 gel, 50 sx. 10 gel, 1 hulls, 120- sx. 60-40 poz., 6% gel. On Oct. 20, top of cement was 150' down, filled to top with redmix.  
 (If additional description is necessary, use BACK of THIS FORM.)

Name of Plugging Contractor Pratt Well Service, Inc. RECEIVED 5893  
 STATE CORPORATION COMMISSION

Address P.O. Box 847 Pratt, Ks. 67124

NOV 15 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corp.

STATE OF Kansas COUNTY OF Pratt

CONSERVATION DIVISION

plugging contractor

Judy Berry (Employee or Operator or Contractor) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 14th day of November, 1989

Dorothy M. Ferguson  
 Notary Public

My Commission Expires: February 6, 1993

DRILLERS LOG

#1 Mueller

CASING RECORD:

10 3/4" cond. pipe  
@ 214' w/ 225 sx cement

4 1/2" @ 4670' w/  
125 sx cement

COMPANY: Hummon Corporation DESCRIPTION:  
CONTRACTOR: Big-H Drilling, Inc. NE SE NW  
COMMENCED: September 29, 1981 Sec. 7-29S-12W  
COMPLETED: October 9, 1981 Pratt County, KS  
TOTAL DEPTH: 468  
ELEVATION: 1901G

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	1974	
Shale & lime	1974	2732	
Lime & shale	2732	4530	
Lime & sand	4530	4569	
Lime & shale	4569	4600	
Lime, shale & sand	4600	4678	
Dolomite	4678	4681	
RTD		4681	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.

*Karen R. Tennis*  
Karen R. Tennis

Subscribed and sworn to before me this 14th day of October, 1981.

SANDRA L. MENDOZA  
STATE NOTARY PUBLIC  
SEDCWICK COUNTY, KANSAS  
MY APPT. EXP. 2/13/82

*Sandra L. Mendoza*  
Notary Public

RECEIVED  
STATE CONSERVATION COMMISSION

SEP 20 1981

CONSERVATION DIVISION  
Wichita, Kansas