

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 7 TWP. 29S RGE. 12 E/W  
Location as in quarters or footage from lines:  
E $\frac{1}{2}$  - NE NW


Lease Owner Hummon Oil Corp.  
Lease Name Stoops Well No. 1  
Office Address 400 One Main Place, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed 3-18-82  
Application for plugging filed 8-30-82  
Plugging commenced 9-6-82  
Plugging completed 9-14-82 11:30  
Reason for abandonment of well or producing formation Dry

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Durant & Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				13 3/8	230	None
				4 $\frac{1}{2}$	4699	3310

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set. Plug back at 4673

Push plug to 4100'  
Sand from 4100' to 4050'  
4 sacks cement from 4050 to 4020  
Dowell pumped in 2 hulls - 20 sacks jell  
200 sacks 50-50 POZ 4% Jell 3% c.c.

Shut in Pressure 400 lb.

RECEIVED  
SEP 15 1982  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Edna R. Margenstern (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Edna R. Margenstern  
Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of Sept., 1982.

My Commission expires: April 4, 1986  
Jessie Hamilton  
Notary Public.