

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give all information completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt

County, Sec. 7 Twp. 29 Rge. (E) 12 (W)

Location as "NE/CNWxSWx" or footage from lines NE NE NE

Lease Owner Strata Drilling, Inc.

Lease Name Pride Well No. 1

Office Address Box 355, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 29 1960

Application for plugging filed May 29 1960

Application for plugging approved May 29 1960

Plugging commenced May 29 1960

Plugging completed May 29 1960

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4675' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole as follows: Bottom plug @ 250' plugged with 15 sacks of cement. 1/2 sacks of hulls; top plug @ 35', plugged with 10 sacks of cement. 1/2 sack of hulls. Plug down May 29, 1960.

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Jim B. McWilliams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jim B. McWilliams
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31th day of May, 1960

My commission expires December 14, 1961

Elaine H. Taylor
Elaine H. Taylor Notary Public.



DRILLERS LOG

CASING: 793.46' of used 8-5/8" surface casing	COMPANY: Strata Drilling, Inc.	DESCRIPTION: NE NE NE Section 7-29-12W Pratt County, Kansas
TOTAL DEPTH: 4675'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 1886' GR 1892' RB
	COMMENCED: May 9, 1960	
	COMPLETED: May 29, 1960	

RECEIVED
STATE CORPORATION COMMISSION

D. & A.

JUN 17 1960


CONSERVATION DIVISION
Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	166	Ran 793.46' of used 8-5/8" surface casing; cemented with 450 sacks of cement, 3% gel and 2% C. C. Cemented @ 784'. Plug down @ 7:15 P. M. 5-10-60. Did not circ. cement. Ran 150 sacks on outside of casing. Circ. cement. Job completed @ 1:15 A. M. 5-11-60. Lost circ. ran 31 joints 7" used casing, 932.66' set @ 930' with 60 sacks of regular cement, 2% gel and 2% C. C. over balanced waiting on more cement. Ran 60 sacks regular, 2% gel and 2% C. C. balanced in plug @ 808' 40 sacks outside, 20 sacks in. Job completed @ 7:30 A. M. 5-14-60.
Sand & Red Bed	166	575	
Red Bed & Shale	575	750	
Shale	750	859	
Red Bed, Shale & Shells	859	1640	
Shale	1640	1767	
Shale & Lime	1767	3842	
Lime	3842	4242	
Lime & Chert	4242	4317	
Lime, Chert & Shale	4317	4326	
Lime	4326	4373	
Lime & Shale	4373	4416	
Lime	4416	4464	
Lime, Chert & Shale	4464	4491	
Lime	4491	4550	
Sand	4550	4567	
Lime	4567	4593	
Lime & Shale	4593	4675	
Total Depth 4675'			<u>DST #1</u> 4280'-4326' tool open 1 hour. Recovered 10' mud. Fair blow declining to weak. All pressures were 0 lbs.
Top Heebner	3637'	(-1745')	<u>DST #2</u> 4427'-4435' tool open 1 hour. Recovered 5' mud. All pressures were 0 lbs.
Top Brown Lime	3817'	(-1925')	
Top Lansing	3836'	(-1944')	
Top Mississippi	4281'	(-2389')	<u>DST #3</u> 4545'-4550' tool open 1 hour. Recovered 470' gas, 376' oil and gas cut salt water. IFP 0 lbs. FFP 180 lbs. BHP 1300 lbs. in 20 min.
Top Kinderhook	4369'	(-2477')	
Top Viola	4423'	(-2531')	
Top Simpson Shale	4535'	(-2643')	
Top Simpson Sand	4542'	(-2650')	
Top Weathered Arbuckle	4638'	(-2746')	Ran Schlumberger Sonic Log.
Top Arbuckle	4646'	(-2754')	D. & A. Plugged May 29, 1960.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 31th day of May, 1960.


Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1961