

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 - 151-21,936-00-00

LEASE NAME Hiskett "B"

WELL NUMBER 3-23

4290' Ft. from S Section Line

4950' Ft. from E Section Line

SEC. 23 TWP. 29S RGE. 11 (W)

COUNTY Pratt

Date Well Completed 6-27-89
9:00 PM

Plugging Commenced 6-27-89

10:45 PM
Plugging Completed 6-27-89

JUN 29 1989

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167
Wichita, Kansas 67278-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, D&A SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-27-89 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole with heavy mud. Plugged with 50 sacks at 640';
50 sacks at 300'; 10 sacks 40' to surface and 15 sacks in rathole.
Used 60/40 Pozmix with 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard L. Mead, President

(Address) P. O. Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1989

Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- HISKETT "B" #3-23
Located: SW NW NW, Section 23-29S-11W, Pratt County, Kansas

OWNER: F. G. Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 20, 1989
COMPLETED: June 27, 1989

TOTAL DEPTH: 4690'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 70 Surface Soil and Sand	Ran 7 joints 8 5/8" Casing. 269.70'
70 - 286 Shale and Clay	pipe set at 281' K.B. Cemented with
286 - 1005 Shale	200 sacks 60/40 Pozmix, 2% gel and
1005 - 1642 Shale and Lime	3% cc. Plug down at 12:15 PM, 6-20-89,
1642 - 1655 Anhydrite	by Howco.
1655 - 4690 Lime and Shale	Plugged.

RECEIVED
STATE CONSERVATION COMMISSION
STATE GEOLOGICAL SURVEY
JUN 29 1989
CONSERVATION DIVISION
Wichita, Kansas

Deviation Surveys: 1° at 2690'
1 1/4° at 4658'