

To: 1 041277
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 151-21,426 -00-00
30' N & 30' W of
C NE SW, SEC. 33, T 29 S, R 11. ~~XX~~
2010 feet from S section line
3330 feet from E section line

12-2
TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company, LLC
Name & Address: P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Rolf Well # 2-33
County Pratt 91.94
Well Total Depth 2829 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 2 Month: 12 Year: 19 97

Plugging proposal received from Thom Pool
(company name) Pratt Well Service (phone) 316-672-2531

Core: 4 1/2" at 2828' w/125 sx cement, PBSD 2806', Perfs at 2762-96'

1st plug set CIBP at 2700' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 2 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2700' with 2 sx cement on top,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2080' of 4 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 12-15-97 I (did / ~~xxxxxx~~) observe this plugging.

INV. NO. 49681

Signed Stephen J. Pfenner (TECHNICIAN)