

1 051385

12-27-91
API NUMBER 15-185-22,026-00-00

287R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW NE, SEC. 14, T 29 S, R 11 W/E
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 0 5056

Lease Name Beat Well # 1-14

Operator: F.G. Holl Company

County Pratt 152.97

Name & Address P.O. Box 780167

Well Total Depth 4707 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 241

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 12 p.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 870' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1991

01-04-81

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton!

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 1-28-91

INV. NO. 30554

EFFECTIVE DATE: 12-15-90

15-151-22,020

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date December 12 1990
month day year

NE NW NE Sec 14 Twp 29 S, Rg 11 East West

OPERATOR: License # 5056
Name: F. G. HOLL COMPANY
Address: P. O. BOX 780167
City/State/Zip: Wichita, Kansas 67278-0167
Contact Person: Elynn H. Nagal
Phone: (316) 684-8481

4950' feet from South line of Section
1650' feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5142
Name: Sterling Drilling Company

County: Pratt
Lease Name: Beat Well #: 1-14
Field Name: Wildcat
Is this a Prorated Field? yes no
Target Formation(s): Indian Cave, Miss, Simpson Sand
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 1785 Est. feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 200'
Surface Pipe by Alternate: 1 2 3
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required: N/A
Projected Total Depth: 4750'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: _____

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. REPAIR
 OWO Disposal WILDCAT CORPORATION COMMISSION
 Seismic; # of Holes _____

If OWO: old well information as follows:
Operator: _____
DEC 6 1990
CONSERVATION DIVISION

RECEIVED
STATE CORPORATION COMMISSION

11N 4 1991

Pusher Vaugh Thompson
SPUD DATE 12-14-90 INIT. R.C
LENGTH SURFACE PLANNED 240'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 3/4" @ 241' CONDUCTOR _____
ANHYDRITE T- B- ELEVATION _____
TD 4707 FORMATION MISS
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____
_____ Arbuckle Plug @ 50 Ft. W/ 50 SX
_____ Hug./Council @ _____ Ft. W/ _____ SX
_____ Anhydrite Base @ 810 Ft. W/ 50 SX
_____ 1/2 Base Anyh. @ _____ Ft. W/ _____ SX
_____ 1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
_____ Bottom Surface @ 300 Ft. W/ 50 SX
_____ 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____
WATER WELL _____ SX (Irr. Well _____ Pond _____
TECHNICIAN R.L DATE 12-14-90 Hauling _____
TYPE OF CEMENT 60/40 6%
STARTING TIME 12:00 (AM/PM) DATE 12-27-90
COMPLETION TIME 2:30 DATE 12-27-90
CEMENT COMPANY Halliburton