

To: 1040824 2-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,177-06-00

C NW NW, SEC. 3, T 29 S, R 11 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Weir Well # A-2

Operator: Kansas Petroleum, Inc.

County Pratt

Name:

Address 225 N. Market, Ste. 310

Well Total Depth 2700 87.75 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:15 p.m. Day: 3 Month: 2 Year: 19 94

Plugging proposal received from Warren Richardson

(company name) Kansas Petroleum, Inc. (phone) 316-775-3613

logs: 4 1/2" at 2698' w/150 sx cement, Perfs at 2650-56'

1st plug sand back to 2600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 100' sx cement.

02-09-94 FEB 9 1994
STATE CORPORATION COMMISSION
WICHITA, KANSAS
CONSERVATION DIVISION
Steve Middleton
(TECHNICIAN)

Plugging Proposal Received by Steve Middleton

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 3 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 2600' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50' sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1540' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED
(if applicable) observe this plugging.

DATE FEB 11 1994

INV. NO. 39916

Signed Stephen J. Pfeiffer
(TECHNICIAN)