

1 061177

12-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,292 - 66-00

C NE NE, SEC. 3, T 29 S, R 11 W/E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4691

Lease Name Nossaman Well # 1

Operator: Hirt Farms Inc.

County Pratt 89.47

Name & Address V-Hirt, R.R. 1, Box 28

Well Total Depth 2753 feet

Sawyer, KS 67134

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:30 a.m. Day: 20 Month: 12 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 2750' PBTB 2704' Perfs at 2674-76', 2684-87'

1st plug sand back to 2620' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1988
12-22-88

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2620' and dumped 4 sx cement on top of

sand through bailer. Stephen J. Pfeifer witnessed this plug,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 2%cc, 2% gel by B.J. Titan. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE DEC 22 1988

INV. NO. 23432

Signed Paul Luthi (TECHNICIAN)