

1 030597

API NUMBER 15- 151-21,726 - 00-05 *R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW SW SW, SEC. 35, T 28 S, R 15 W/EX  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Bryan Well # 1

Operator: VAC Petroleum Company  
Name & Address 333 North Rock Road, Suite 105  
Wichita, KS 67206

County Pratt 156.23

Well Total Depth 4810 Simpson feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 430 /

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Company License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 10:00 pm Day: 2 Month: November Year: 1985

Plugging proposal received from Mark Guinn

(company name) Aldebaran (phone) 316-685-5372

Remarks: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 900' approx. Elevation N/A

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement. Plug water well with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 12:30 am Day: 3 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement, 2nd plug at 460' with 50 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- ce-ent to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement, and plugged water well from bottom to top with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

RECEIVED

INVOICED

DATE DEC 10 1985

DEC 5 1985

Signed *Steve Luthi* (TECHNICIAN)

INV. NO. 11390

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84