

1 060645

API NUMBER 15- 151-21,673-00-90 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE NW, SEC. 34, T 28 S, R 15 W

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Moore Well # 2

Operator: VAC Petroleum Co.

County Pratt 157.63

Name & Address 333 North Rock Road, Suite 105

Well Total Depth 4850 (Arbuckle) feet

Wichita, KS 67206

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Co. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 6:00 am Day: 19 Month: August Year: 19 85

Plugging proposal received from Wayne Boughner

(company name) Aldebaran (phone) 316-685-5372

Elevation NA

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 925'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' out of the surface pipe

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 am Day: 19 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 950' with 50 sx cement, 2nd plug at 470' with 50 sx cement,

3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(check, did not) observe this plugging.

DATE AUG 28 1985

RECEIVED

STATE CORPORATION COMMISSION

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 9832

AUG 28 1985